

**ADVERTISEMENT FOR BIDS**  
**WINSTON-SALEM / FORSYTH COUNTY UTILITIES**

Pursuant to N.C.G.S. 143-128 and 129, sealed bid proposals endorsed “**Wallburg Road Lift Station Design-Build project, RFQ25297**” will be received by City/County Purchasing, 101 N. Main Street, Winston-Salem, NC 27101 until **2:00 PM, June 17, 2025**, at which time all bids will be received at [bids@cityofws.org](mailto:bids@cityofws.org). Should three bids not be received, the bid will be re-advertised. The City reserves the right to reject any or all proposals.

Contractors must be properly licensed as required by Chapter 87 of the North Carolina General Statutes - at time of bid opening - to perform the work described herein as the general/prime contractor.

As a design-build project, the contractor will be chosen by qualifications-based selection, with criteria being MWBE participation plan, project experience, project approach, and qualifications of personnel assigned to the project, including any subconsultants. Current schedule: Preconstruction start August 2025 with one year for construction beginning May 2026.

The Issuing Office of HDR Engineering, Inc. of the Carolinas, 100 North Main Street, Suite 1500, Winston-Salem, NC 27101. Contact Will Shull at [Will.Shull@hdrinc.com](mailto:Will.Shull@hdrinc.com) or 704-473-2792 for the bidding documents.

Neither Owner nor Engineer has any responsibility for the accuracy, completeness, or sufficiency of any Bidding Documents obtained from any source other than the Issuing Office. Obtaining these documents from any source other than the Issuing Office may result in obtaining incomplete and inaccurate information. Obtaining these documents from any source other than the Issuing Office may also result in failure to receive any addenda, corrections, or other revisions to the Bidding Documents that may be issued.

The project consists of constructing a new pump station and associated lines to accommodate wastewater flow. The required lines include approximately 9000 linear feet (lf) of 12-inch gravity sewer and approximately 4000 lf of 10- inch force main. The force main will terminate at a future manhole located just east of the intersection of Wallburg Road and Sherlie Weavil Road. The pump station will be a duplex submersible type with a firm pumping capacity of 660 gallons per minute (gpm).

For technical questions regarding this project, submit questions **in writing only** to: Jordan Toney at [jordant@cityofws.org](mailto:jordant@cityofws.org). The End of Question Period is 5:00 PM, June 6, 2025.

\*\*Notice of Pre-Proposal Conference\*\*

A project information meeting will be held at **2:00 PM, June 4, 2025**, in Conference Room 348, City Hall, 101 N. Main Street, Winston-Salem, NC 27101 to summarize the project scope, answer any bidder questions, for this project.

## **BID QUANTITIES**

**(subject to change - refer to Bid Form in Project Manual)**