


See Sheet 1-A For Index Of Sheets
See Sheet 1-B For Conventional Sheet Symbols



VICINITY MAP

NOT TO SCALE

WAKE COUNTY

TOWN OF FUQUAY-VARINA

ALSTON RIDGE GREENWAY FUQUAY-VARINA, NORTH CAROLINA 27526

TYPE OF WORK: GRADING, BOARDWALK, DRAINAGE, PAVING, SIGNING, AND MARKINGS
LENGTH OF PROJECT: APPROX. 0.46 MILES OF NEW LOCATION GREENWAY
APPROX. 0.03 MILES OF BOARDWALK

FINAL PLANS

UTILITY AND GOVERNING AGENCIES CONTACT LIST:

WATER COMPANY

TOWN OF FUQUAY-VARINA UTILITIES DEPT.
134 N. MAIN STREET
FUQUAY-VARINA, NC 27526
(919) 567-3911 TEL
CONTACT: JAY T. MEYERS

DEPARTMENT OF TRANSPORTATION

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
2612 NORTH DUKE STREET
DURHAM, NC 27704
(919) 854-6236 TEL
CONTACT: RAYMOND HAYES

SANITARY SEWER COMPANY

TOWN OF FUQUAY-VARINA UTILITIES DEPT.
134 N. MAIN STREET
FUQUAY-VARINA, NC 27526
(919) 567-3911 TEL
CONTACT: JAY T. MEYERS

PLANNING DEPARTMENT

TOWN OF FUQUAY-VARINA PLANNING DEPARTMENT
134 N. MAIN STREET
FUQUAY-VARINA, NORTH CAROLINA 27526
(919) 753-1870 TEL
CONTACT: PAM DAVISON

FIRE CHIEF

FUQUAY-VARINA FIRE DEPARTMENT
134 N. MAIN STREET
FUQUAY-VARINA, NORTH CAROLINA 27526
(919) 753-1002 TEL
CONTACT: ANTHONY MAULDIN

POLICE DEPARTMENT

TOWN OF FUQUAY-VARINA POLICE DEPARTMENT
134 N. MAIN STREET
FUQUAY-VARINA, NORTH CAROLINA 27526
(919) 552-1416 TEL
CHIEF OF POLICE: LAURA FAHNESTOCK

EROSION CONTROL

NCDEQ
DIVISION OF LAND RESOURCES
3800 BARETT DRIVE
RALEIGH, NORTH CAROLINA 27609
(919) 791-4200 TEL
CONTACT: TBD

ENGINEERING DEPARTMENT

TOWN OF FUQUAY-VARINA
ENGINEERING DEPARTMENT
134 N. MAIN STREET
FUQUAY-VARINA, NORTH CAROLINA 27526
(919) 567-1039 TEL
CONTACT: MATT POLING

TOWN:

TOWN OF FUQUAY-VARINA
134 N. MAIN STREET
FUQUAY-VARINA, NC 27526
(919) 753-1035 TEL
CONTACT: MATTHEW B. POLING, P.E.

ENGINEER:

KIMLEY-HORN AND ASSOCIATES, INC.
300 S MAIN STREET, SUITE 212
HOLLY SPRINGS, NC 27540
(919) 653-2905 TEL
bryan.vickery@kimley-horn.com
CONTACT: BRYAN VICKERY, P.E.

SURVEYOR:

McKIM & CREED
1730 VARSITY DRIVE
VENTURE IV BUILDING, SUITE 500
RALEIGH, NC 27606
(919) 233-8091 TEL
CONTACT: JEFF AKER, PLS

PREPARED IN THE OFFICE OF:

Kimley»Horn


© 2024

NC LICENSE #F-0102
300 S MAIN ST, SUITE 212
HOLLY SPRINGS, NORTH CAROLINA 27540
PHONE: (919) 653-2905


CLEARING ON THIS PROJECT SHALL BE PERFORMED BY THE LIMITS ESTABLISHED BY METHOD II. THIS DOCUMENT, TOGETHER WITH THE CONCEPTS AND DESIGNS PRESENTED HEREIN, AS AN INSTRUMENT OF SERVICE, IS INTENDED ONLY FOR THE SPECIFIC PURPOSE AND CLIENT FOR WHICH IT WAS PREPARED. REUSE OF AND IMPROPER RELIANCE ON THIS DOCUMENT WITHOUT WRITTEN AUTHORIZATION AND ADAPTATION BY KIMLEY-HORN AND ASSOCIATES, INC. SHALL BE WITHOUT LIABILITY TO KIMLEY-HORN AND ASSOCIATES, INC.

DATE	FILE NUMBER	SHEET NUMBER	TOTAL SHEETS
8/13/2024		1	42

COPYRIGHT © 2024




PROJECT GRAPHIC SCALES



PLANS PREPARED BY:

Kimley»Horn

300 S MAIN ST, SUITE 212
HOLLY SPRINGS, NC 27540
PHONE: (919) 677-2000
FAX: (919) 677-2050
NC LICENSE #F-0102
© 2024



NO.	DATE	REVISIONS

PLANS PREPARED FOR:
FUQUAY-VARINA
TOWN OF FUQUAY-VARINA

PROJECT:
TIP: BL-00092
ALSTON RIDGE GREENWAY


TITLE SHEET

KHA PROJECT:
012622018
DATE:
8/13/2024

FINAL PLANS

1

K:\RAL_Roadway\012622018.A - Alston Ridge Greenway\Plan\Plan Sheets\Alston_1.sxdgn 8/13/2024



NO.	DATE	REVISIONS

PLANS PREPARED FOR:

FUQUAY-VARINA
north carolina

TOWNSHIP OF FUQUAY-VARINA

PROJECT:

TIP: BL-00092
ALSTON RIDGE GREENWAY

TITLE:

ALIGNMENT
CURVE DATA

KHA PROJECT:

012622018

DATE:

8/13/2024

FINAL PLANS

-L-

<i>PI Sta 13+00.72</i>	<i>PI Sta 14+77.82</i>	<i>PI Sta 15+83.42</i>
$\Delta = 13^{\circ} 14' 59.3''$ (RT)	$\Delta = 21^{\circ} 19' 16.1''$ (LT)	$\Delta = 24^{\circ} 07' 08.7''$ (RT)
$D = 14^{\circ} 19' 26.2''$	$D = 14^{\circ} 19' 26.2''$	$D = 38^{\circ} 11' 49.9''$
$L = 92.50'$	$L = 148.85'$	$L = 63.14'$
$T = 46.46'$	$T = 75.30'$	$T = 32.05'$
$R = 400.00'$	$R = 400.00'$	$R = 150.00'$

-L-

<i>PI Sta 18+83.62</i>	<i>PI Sta 20+69.51</i>	<i>PI Sta 22+22.79</i>	<i>PI Sta 24+26.61</i>
$\Delta = 75^{\circ} 29' 52.7''$ (LT)	$\Delta = 83^{\circ} 10' 06.4''$ (RT)	$\Delta = 62^{\circ} 09' 27.8''$ (LT)	$\Delta = 26^{\circ} 48' 29.9''$ (RT)
$D = 49^{\circ} 49' 20.7''$	$D = 71^{\circ} 37' 11.0''$	$D = 71^{\circ} 37' 11.0''$	$D = 38^{\circ} 11' 49.9''$
$L = 151.53'$	$L = 116.13'$	$L = 86.79'$	$L = 70.18'$
$T = 89.04'$	$T = 70.99'$	$T = 48.22'$	$T = 35.75'$
$R = 115.00'$	$R = 80.00'$	$R = 80.00'$	$R = 150.00'$


-L-

<i>PI Sta 27+11.62</i>	<i>PI Sta 28+81.18</i>	<i>PI Sta 30+73.49</i>	<i>PI Sta 32+33.39</i>
$\Delta = 32^{\circ} 44' 22.8''$ (LT)	$\Delta = 34^{\circ} 09' 29.6''$ (RT)	$\Delta = 92^{\circ} 05' 51.2''$ (LT)	$\Delta = 87^{\circ} 24' 21.6''$ (RT)
$D = 11^{\circ} 27' 33.0''$	$D = 57^{\circ} 17' 44.8''$	$D = 95^{\circ} 29' 34.7''$	$D = 71^{\circ} 37' 11.0''$
$L = 285.71'$	$L = 59.62'$	$L = 96.44'$	$L = 122.04'$
$T = 146.87'$	$T = 30.72'$	$T = 62.24'$	$T = 76.46'$
$R = 500.00'$	$R = 100.00'$	$R = 60.00'$	$R = 80.00'$


K:\PAL_Roadway\012622018A - Alston Ridge Greenway\Plan\Plan_Sheets\Alston_Curve Data.dgn

8/13/2024

- NOTES:
1. ALL WOOD TO BE NO. 2 SOUTHERN YELLOW PINE, SEE SPECIFICATIONS.
 2. ALL FENCE AND GATE HARDWARE TO BE GALVANIZED. SEE SPECIFICATIONS.
 3. ALL NAILS AND STAPLES TO BE GALVANIZED. SEE SPECIFICATIONS.
 4. SLOPE TOP OF CONCRETE FOOTING AWAY FROM POST.
 5. FENCING TO BE FIELD CONFIRMED BY ENGINEER/OWNER PRIOR TO INSTALLATION



DETAIL 1 – TIMBER RAILING




DETAIL 2 – WOOD BENCH

K:\RAL_Roadway\012622018A - Alston Ridge Greenway\Plan\Plan Sheets\Alston.tpd.dgn 8/13/2024

PLANS PREPARED BY:

Kimley»Horn

300 S MAIN ST, SUITE 202
 HOLLY SPRINGS, NC 27540
 PHONE: (919) 677-2000
 FAX: (919) 677-2050
 NC LICENSE #P-0002
 ©2024



NO.	DATE	REVISIONS

PLANS PREPARED FOR:
FUQUAY-VARINA
north carolina
 TOWN OF FUQUAY-VARINA








PROJECT:
ALSTON RIDGE GREENWAY

TITLE:
DETAIL SHEET

KHA PROJECT:
012622018
 DATE:
8/13/2024

FINAL PLANS

2B



NO.	DATE	REVISIONS

PLANS PREPARED FOR:
FUQUAY-VARINA
north carolina
TOWN OF FUQUAY-VARINA


PROJECT:
TIP: BL-00092
ALSTON RIDGE GREENWAY

TITLE:
DRAINAGE DETAILS


KHA PROJECT:
012622018
DATE:
8/13/2024

FINAL PLANS

K:\RAL_Roadway\012622018A - Alston Ridge Greenway\Plan\Plan Sheets\Alston_Tip.dgn 8/13/2024



NO.	DATE	REVISIONS



PLANS PREPARED FOR:
FUQUAY-VARINA
TOWN OF FUQUAY-VARINA


PROJECT:
TIP: BL-00092
ALSTON RIDGE GREENWAY

TITLE:
PLAN AND PROFILE SHEET

KHA PROJECT:
012622018
DATE:
10/25/2024

FINAL PLANS

K:\RAL_Roadway\012622018A - Alston Ridge Greenway\Plan\Plan Sheets\Alston_psh_5.dgn
10/25/2024



NO.	DATE	REVISIONS



PLANS PREPARED FOR:
FUQUAY-VARINA
 north carolina
 TOWN OF FUQUAY-VARINA

PROJECT:
 TIP: BL-00092
ALSTON RIDGE GREENWAY


TITLE:
PLAN AND PROFILE SHEET

KHA PROJECT:
012622018
 DATE:
8/13/2024

FINAL PLANS



K:\RAL_Roadway\012622018A - Alston Ridge Greenway\Plan\Plan Sheets\Alston_psh.dgn
 8/13/2024



NO.	DATE	REVISIONS

PLANS PREPARED FOR:

 FUQUAY-VARINA
 north carolina
 TOWN OF FUQUAY-VARINA


PROJECT:
 TIP: BL-00092
 ALSTON RIDGE GREENWAY

TITLE:
 PAVEMENT MARKING
 AND SIGNING PLAN


KHA PROJECT:
012622018
 DATE:
10/30/2024

FINAL PLANS

PM-3



END PROJECT
 END 10' WIDE ASPHALT GREENWAY
 TIE TO EXISTING GREENWAY
 -L- POT Sta. 34+39.59



MATCHLINE -L- STA 27+50.00
 (SEE PLAN SHEET PM-2)

SIGN NUMBER: D1-2b TYPE: D QUANTITY: 1 SIGN WIDTH: 3'-0" HEIGHT: 1'-0" TOTAL AREA: 3.0 Sq.Ft. BORDER TYPE: FLUSH RECESS: 0.0" WIDTH: 0.38" RADII: 1.5" NO. Z BARS: LENGTH:	BACKG COLOR: GREEN COPY COLOR: WHITE <table border="1"> <thead> <tr> <th>SYMBOL</th> <th>X</th> <th>Y</th> <th>WID</th> <th>HT</th> </tr> </thead> <tbody> <tr> <td>AR_Type D</td> <td>2.5</td> <td>7.5</td> <td>2</td> <td>3</td> </tr> <tr> <td>Bicycle</td> <td>8.6</td> <td>7.2</td> <td>5.2</td> <td>3</td> </tr> <tr> <td>Bicycle</td> <td>2.5</td> <td>2.2</td> <td>5.2</td> <td>3</td> </tr> <tr> <td>AR_Type D</td> <td>30.5</td> <td>2.5</td> <td>2</td> <td>3</td> </tr> </tbody> </table> MAT'L: 0.125" (3.2 mm) ALUMINUM	SYMBOL	X	Y	WID	HT	AR_Type D	2.5	7.5	2	3	Bicycle	8.6	7.2	5.2	3	Bicycle	2.5	2.2	5.2	3	AR_Type D	30.5	2.5	2	3	DESIGN BY: LCK PROJECT ID: BL-0092 CHECKED BY: BTV Jun 05, 2024 DIV: 05
SYMBOL	X	Y	WID	HT																							
AR_Type D	2.5	7.5	2	3																							
Bicycle	8.6	7.2	5.2	3																							
Bicycle	2.5	2.2	5.2	3																							
AR_Type D	30.5	2.5	2	3																							

BORDER
R=1.5"
TH=0.38"
IN=0.0"

Spacing Factor is 1 unless specified otherwise

LETTER POSITIONS

Letter spacings are to start of next letter


	T	e	a	i	L	o	k	e	R	o	a	d	Series/Size Text Length		
17	1.1	1.1	1.1	0.3	2	1.1	1.1	1.1	1	2	1.2	1.1	1	2.5	C 2000 16.5
	B	o	s	s	L	o	k	e	P	o	r	k	C 2000 16.7		
9.7	1.2	1.1	0.9	0.8	2	1.1	1.1	1.2	1	2	1.3	1.1	0.8	1.1	9.7

FILENAME: Guidesign_English_8-2-13

NORTH CAROLINA D.O.T. SIGN DETAIL


- PROJECT NOTES**
- DISPOSAL OF SIGN, D, E, OR F
 - DISPOSAL OF SIGN SYSTEM, U-CHANNEL
 - DISPOSAL OF SUPPORT, U-CHANNEL
 - SIGN ERECTION, RELOCATE, SIGN TYPE F
 - SIGN ERECTION, RELOCATE, SIGN TYPE E

K:\PAL_Roadway\012622018A - Alston Ridge Greenway\Plan\PM-3 & Signing\Alston_ump_psh.dgn
 10/30/2024



NAD 83 / NA 2011

Total Disturbed Area (shaded) = 3.10 acres



NO.	DATE	REVISIONS

PLANS PREPARED FOR:
FUQUAY-VARINA
north carolina
TOWN OF FUQUAY-VARINA

PROJECT:
TIP: BL-00092
ALSTON RIDGE GREENWAY

TITLE:
DENUDED AREAS

KHA PROJECT:
012622018
DATE:
8/13/2024

FINAL PLANS

ERO-1

K:\PAL_Roadway\012622018A - Alston Ridge Greenway\Plan\Erosion Control\Alston_ero_DNA_dsh.dgn
8/13/2024

NARRATIVE

Project Description

The Alston Ridge Greenway is a multi-use trail system for bicycle and pedestrian use. It is being constructed by the Town of Fuquay-Varina to connect and access numerous recreational destinations in Fuquay-Varina. Approximately 3.10 acres will be disturbed during the construction of this project. Also, approximately 2.55 acres will be vegetatively stabilized with grass and permanent plantings.

Alston Ridge Greenway is located in Wake County, Fuquay-Varina, NC. The project site runs along Basal Creek as it connects to Bass Lake. The greenway travels through multiple residential areas, beginning at Old Addams Road, where the trail will connect to the existing greenway, and terminating near Briarglen Lane, where it will connect to the existing Bass Lake Trail.

Site Description

The site has a downward slope that travels from the western side of the project to the eastern side. The site has some existing sanitary sewer pipes and manholes. Land use along the project is predominantly residential with some areas along Alston Pond properties. Drainage from the project site sheet flows down the slope of the site and eventually flows through Basal Creek into Bass Lake and eventually into the Neuse River Watershed, thus no new drainage patterns will be introduced. Pre-construction runoff equals Post-construction runoff for all existing system outlets that are to be retained. The fill slopes and drainage ditches around the project appear to be stable and do not show signs of significant erosion soils.


Soils

The soil types throughout the project limits are mostly sandy loam (AaA, BbA, PaE, WeD, and WeE).

--- PROJECT DENUDED AREAS

IMPERVIOUS AND PERVIOUS SURFACES IN ALSTON RIDGE GREENWAY DISTURBED AREAS

PROPOSED IMPERVIOUS SURFACE = 0.55 AC
PROPOSED PERVIOUS SURFACE = 2.55 AC



NOTE: SLOPES ON THIS PROJECT ARE PRIMARILY 2:1 AND 3:1. CONTRACTOR SHALL PROVIDE SOIL STABILIZATION ON ALL SLOPES WITHIN 7 DAYS OR AS REQUIRED BY NPDES GENERAL STORMWATER PERMIT. REFER TO CROSS SECTIONS AND MATTING SUMMARY SHEET.

LIMITS OF DISTURBANCE SHOWN SHADED ON SHEET EC-1. SYMBOLOGY IS SHOWN IN LEGEND AND IT IS DELINEATED ON THE REMAINING EROSION CONTROL PLAN SHEETS

ROCK CHECK DAMS TO BE INSTALLED AND MAINTAINED WHEN UNSTABLE AND SEDIMENT LADEN SOIL IS DRAINING TO STRUCTURES. CONTRACTOR TO COORDINATE WITH TOWN INSPECTOR TO DETERMINE WHEN ROCK CHECK DAMS MAY BE REPLACED BY WATTLES UPON PARTIAL STABILIZATION OF SOIL.

BOARDWALK AND CULVERT EROSION CONTROL PHASING:

- CONTRACTOR TO INSTALL ALL EROSION CONTROL MEASURES BEFORE ANY CLEARING AND GRUBBING IS PERFORMED.**
- CONTRACTOR TO ACCESS BOARDWALK AND CULVERT LOCATIONS USING PROPOSED GREENWAY PATH FOOTPRINT. USE MUD MATS (SEE EROSION CONTROL DETAILS) IN WETLAND AREAS AND OTHER LOW AREAS TO LIMIT IMPACTS.**
- CONTRACTOR TO DEWATER EXCAVATED AREAS AS NEEDED USING IMPERVIOUS DIKES, SPECIAL STILLING BASINS, AND BYPASSING PUMPING (DEWATERING METHOD INCIDENTAL TO BOARDWALK INSTALLATION).**
- AFTER BOARDWALK AND CULVERTS ARE SET, CONTRACTOR IS TO STABILIZE ALL DISTURBED AREAS AND STREAM BANK SLOPES USING EROSION CONTROL MATTING, SEEDING (SEE SHEET ERO-9), AND MULCH TO MAINTAIN A VIGOROUS, DENSE, VEGETATIVE COVER.**

PIPES SHALL BE INSTALLED IN THE DRY (WITH A MIN. 3 DAYS OF DRY WEATHER DURING INSTALLATION.) CONTACT ENGINEER AND INSPECTOR 24 HOURS PRIOR TO INSTALLATION OF STORMDRAIN SYSTEMS.

THESE EROSION AND SEDIMENT CONTROL PLANS COMPLY WITH THE REGULATIONS SET FORTH BY THE NCG-010000 GENERAL CONSTRUCTION PERMIT EFFECTIVE MARCH 31, 2024 ISSUED BY THE NORTH CAROLINA DEPARTMENT OF ENVIRONMENT AND NATURAL RESOURCES DIVISION OF WATER QUALITY.


SELF-INSPECTIONS AND SELF-MONITORING SHALL BE CONDUCTED IN ACCORDANCE WITH THE CONDITIONS OF THE NPDES PERMIT NO. NCG010000 AND NORTH CAROLINA GENERAL STATUTE 113A-54.1(e) AND 15A NCAC 04B.0131

THIS SHEET REPRESENTS THE CLEARING AND GRUBBING PHASE OF THE PROJECT. SEE SHEET ERO-5 FOR THE CONSTRUCTION PHASE.

PLANS PREPARED BY:

Kimley Horn

300 S MAIN ST, SUITE 202
HOLLY SPRINGS, NC 27540
PHONE: (919) 877-2000
FAX: (919) 677-2050
NC LICENSE # 0002
© 2024



NO.	DATE	REVISIONS

PLANS PREPARED FOR:
FUQUAY-VARINA
north carolina
TOWN OF FUQUAY-VARINA

PROJECT:
TIP: BL-00092
ALSTON RIDGE GREENWAY


TITLE:
EROSION CONTROL PLANS

KHA PROJECT:
012622018

DATE:
8/13/2024


FINAL PLANS

ERO-2



LEGEND

CONSTRUCTION LIMIT	C --- F	LIMITS OF DISTURBANCE (LABELED ON PLANS)	-----
TEMPORARY SILT FENCE (SEE DETAIL SHEETS)		STORM DRAIN INLET PROTECTION (SEE DETAIL SHEETS)	[Symbol]
SPECIAL SEDIMENT CONTROL FENCE / SILT FENCE OUTLET (SEE DETAIL SHEETS)	[Symbol]	TEMPORARY ROCK SILT CHECK, TYPE A (SEE NCDOT STD.16.33.01)	[Symbol]
TEMPORARY CONSTRUCTION ENTRANCE (SEE NCDOT STD.16.07.01)	[Symbol]	TEMPORARY ROCK SILT CHECK, TYPE B (SEE DETAIL SHEETS)	[Symbol]
ROCK PIPE INLET SEDIMENT TRAP, TYPE B (SEE NCDOT STD.16.35.02)	[Symbol]	TREE PROTECTION (SEE DETAIL SHEETS)	[Symbol]
CONCRETE WASHOUT (SEE DETAIL SHEETS)	[Symbol]	WATTLE (SEE DETAIL SHEETS)	[Symbol]
OUTLET PROTECTION (SEE DETAIL SHEETS)	[Symbol]	EXISTING CONTOUR	-----
		PROPOSED CONTOUR	-----



NPDES GENERAL STORMWATER PERMIT SOIL STABILIZATION TIMEFRAMES

SITE DESCRIPTION	STABILIZATION TIME	TIMEFRAME EXCEPTIONS
PERIMETER DIKES, SWALES, DITCHES AND SLOPES	7 DAYS	NONE
HIGH QUALITY WATER (HOW) ZONES	7 DAYS	NONE
SLOPES STEEPER THAN 3H	7 DAYS	IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2H, 14 DAYS ARE ALLOWED.
SLOPES 3H OR FLATTER	14 DAYS	7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH.
ALL OTHER AREAS WITH SLOPES FLATTER THAN 4H	14 DAYS	NONE, EXCEPT FOR PERIMETERS AND HOW ZONES.

- GENERAL NOTES (TYPICAL ALL SHEETS):**
- WHERE SILT FENCES ARE LOCATED BELOW STORM DRAIN OUTLETS, THEIR LOCATIONS MUST BE MODIFIED AS THE STORM DRAINS ARE INSTALLED SO THAT THE FENCES WILL PASS OVER THE PIPE OUTLETS.
 - SILT FENCE OUTLET MUST BE ADDED IN THE FIELD WHENEVER LOW POINTS ARE ENCOUNTERED ALONG SILT FENCE RUNS.
 - USE ROLLED EROSION CONTROL PRODUCTS ON ALL CUT/FILL SLOPES INCLUDING BASINS AS NECESSARY FOR STABILIZATION
 - DO NOT ALLOW CONCRETE DUST/WASTE/WASTEWATER INTO STORM DRAIN OR OFF-SITE. ALL SEDIMENT MUST BE CLEANED OFF THE ROADWAY BY DRY SWEEPING METHODS ONLY. WATER MUST NOT BE USED TO WASH SEDIMENT OFF OF ROADS, DRIVEWAYS, OR PARKING LOTS.
 - MINIMIZE BUFFER DISTURBANCE AS MUCH AS POSSIBLE. WORK WITHIN BUFFER ZONE SHOULD BE SEQUENCED TO MINIMIZE THE LENGTH OF TIME THAT DISTURBED AREAS ARE EXPOSED.

- GENERAL NOTES (CONT) (TYPICAL ALL SHEETS):**
- STREAM BANK STABILIZATION SHOULD BE PHASED SO THAT EACH DAY'S WORK IS COMPLETED AND ADEQUATELY STABILIZED AT THE END OF EACH WORK DAY.
 - ADEQUATE TEMPORARY SEDIMENT CONTROLS SHALL BE PROVIDED AT THE END OF EACH WORK DAY AT ALL STREAM CROSSINGS UNTIL ADEQUATE PERMANENT GROUND COVER IS PROVIDED.

K:\RAL_Roadway\012622018A - Alston Ridge Greenway\Plan\Erosion Control\Alston_ero_pst_4_C&G.dgn 8/13/2024

NOTE: SLOPES ON THIS PROJECT ARE PRIMARILY 2:1 AND 3:1. CONTRACTOR SHALL PROVIDE SOIL STABILIZATION ON ALL SLOPES WITHIN 7 DAYS OR AS REQUIRED BY NPDES GENERAL STORMWATER PERMIT. REFER TO CROSS SECTIONS AND MATTING SUMMARY SHEET.

LIMITS OF DISTURBANCE SHOWN SHADED ON SHEET EC-1. SYMBOLOGY IS SHOWN IN LEGEND AND IT IS DELINEATED ON THE REMAINING EROSION CONTROL PLAN SHEETS

ROCK CHECK DAMS TO BE INSTALLED AND MAINTAINED WHEN UNSTABLE AND SEDIMENT LADEN SOIL IS DRAINING TO STRUCTURES. CONTRACTOR TO COORDINATE WITH CITY INSPECTOR TO DETERMINE WHEN ROCK CHECK DAMS MAY BE REPLACED BY WATTLES UPON PARTIAL STABILIZATION OF SOIL.

BOARDWALK AND CULVERT EROSION CONTROL PHASING:

- CONTRACTOR TO INSTALL ALL EROSION CONTROL MEASURES BEFORE ANY CLEARING AND GRUBBING IS PERFORMED.**
- CONTRACTOR TO ACCESS BOARDWALK AND CULVERT LOCATIONS USING PROPOSED GREENWAY PATH FOOTPRINT. USE MUD MATS (SEE EROSION CONTROL DETAILS) IN WETLAND AREAS AND OTHER LOW AREAS TO LIMIT IMPACTS.**
- CONTRACTOR TO DEWATER EXCAVATED AREAS AS NEEDED USING IMPERVIOUS DIKES, SPECIAL STILLING BASINS, AND BYPASSING PUMPING (DEWATERING METHOD INCIDENTAL TO BOARDWALK INSTALLATION).**
- AFTER BOARDWALK AND CULVERTS ARE SET, CONTRACTOR IS TO STABILIZE ALL DISTURBED AREAS AND STREAM BANK SLOPES USING EROSION CONTROL MATTING, SEEDING (SEE SHEET ERO-9), AND MULCH TO MAINTAIN A VIGOROUS, DENSE, VEGETATIVE COVER.**

PIPES SHALL BE INSTALLED IN THE DRY (WITH A MIN. 3 DAYS OF DRY WEATHER DURING INSTALLATION.) CONTACT ENGINEER AND INSPECTOR 24 HOURS PRIOR TO INSTALLATION OF STORMDRAIN SYSTEMS.

THESE EROSION AND SEDIMENT CONTROL PLANS COMPLY WITH THE REGULATIONS SET FORTH BY THE NCG-010000 GENERAL CONSTRUCTION PERMIT EFFECTIVE MARCH 31, 2024 ISSUED BY THE NORTH CAROLINA DEPARTMENT OF ENVIRONMENT AND NATURAL RESOURCES DIVISION OF WATER QUALITY.

SELF-INSPECTIONS AND SELF-MONITORING SHALL BE CONDUCTED IN ACCORDANCE WITH THE CONDITIONS OF THE NPDES PERMIT NO. NCG010000 AND NORTH CAROLINA GENERAL STATUTE 113A-54.1(e) AND 15A NCAC 04B.0131


THIS SHEET REPRESENTS THE CLEARING AND GRUBBING PHASE OF THE PROJECT. SEE SHEET ERO-7 FOR THE CONSTRUCTION PHASE.

PLANS PREPARED BY:

Kimley»Horn


300 S MAIN ST, SUITE 202
HOLLY SPRINGS, NC 27540
PHONE: (919) 677-2000
FAX: (919) 677-2050
NC LICENSE #F-0002
© 2024

SEAL



LEGEND

CONSTRUCTION LIMIT	C - F	LIMITS OF DISTURBANCE (LABELED ON PLANS)	---
TEMPORARY SILT FENCE (SEE DETAIL SHEETS)		STORM DRAIN INLET PROTECTION (SEE DETAIL SHEETS)	□
SPECIAL SEDIMENT CONTROL FENCE / SILT FENCE OUTLET (SEE DETAIL SHEETS)	∇	TEMPORARY ROCK SILT CHECK, TYPE A (SEE NCDOT STD.1633.01)	▣
TEMPORARY CONSTRUCTION ENTRANCE (SEE NCDOT STD.1607.01)	▣	TEMPORARY ROCK SILT CHECK, TYPE B (SEE DETAIL SHEETS)	▶
ROCK PIPE INLET SEDIMENT TRAP, TYPE B (SEE NCDOT STD.1635.02)	⊙	TREE PROTECTION (SEE DETAIL SHEETS)	⌒
CONCRETE WASHOUT (SEE DETAIL SHEETS)	□	WATTLE (SEE DETAIL SHEETS)	⌒
OUTLET PROTECTION (SEE DETAIL SHEETS)	⌒	EXISTING CONTOUR	- - -
		PROPOSED CONTOUR	---



NPDES GENERAL STORMWATER PERMIT SOIL STABILIZATION TIMEFRAMES

SITE DESCRIPTION	STABILIZATION TIME	TIMEFRAME EXCEPTIONS
PERIMETER DIKES, SWALES, DITCHES AND SLOPES	7 DAYS	NONE
HIGH QUALITY WATER (HOW) ZONES	7 DAYS	NONE
SLOPES STEEPER THAN 3H	7 DAYS	IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2H, 14 DAYS ARE ALLOWED.
SLOPES 3H OR FLATTER	14 DAYS	7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH.
ALL OTHER AREAS WITH SLOPES FLATTER THAN 4H	14 DAYS	NONE, EXCEPT FOR PERIMETERS AND HOW ZONES.

GENERAL NOTES (TYPICAL ALL SHEETS):

- WHERE SILT FENCES ARE LOCATED BELOW STORM DRAIN OUTLETS, THEIR LOCATIONS MUST BE MODIFIED AS THE STORM DRAINS ARE INSTALLED SO THAT THE FENCES WILL PASS OVERTHE PIPE OUTLETS.
- SILT FENCE OUTLET MUST BE ADDED IN THE FIELD WHENEVER LOW POINTS ARE ENCOUNTERED ALONG SILT FENCE RUNS.
- USE ROLLED EROSION CONTROL PRODUCTS ON ALL CUT/FILL SLOPES INCLUDING BASINS AS NECESSARY FOR STABILIZATION
- DO NOT ALLOW CONCRETE DUST/WASTE/WASTEWATER INTO STORM DRAIN OR OFF-SITE. ALL SEDIMENT MUST BE CLEANED OFF THE ROADWAY BY DRY SWEEPING METHODS ONLY. WATER MUST NOT BE USED TO WASH SEDIMENT OFF OF ROADS, DRIVEWAYS, OR PARKING LOTS.
- MINIMIZE BUFFER DISTURBANCE AS MUCH AS POSSIBLE. WORK WITHIN BUFFER ZONE SHOULD BE SEQUENCED TO MINIMIZE THE LENGTH OF TIME THAT DISTURBED AREAS ARE EXPOSED.

GENERAL NOTES (CONT) (TYPICAL ALL SHEETS):

- STREAM BANK STABILIZATION SHOULD BE PHASED SO THAT EACH DAY'S WORK IS COMPLETED AND ADEQUATELY STABILIZED AT THE END OF EACH WORK DAY.
- ADEQUATE TEMPORARY SEDIMENT CONTROLS SHALL BE PROVIDED AT THE END OF EACH WORK DAY AT ALL STREAM CROSSINGS UNTIL ADEQUATE PERMANENT GROUND COVER IS PROVIDED.

PLANS PREPARED FOR:

FUQUAY-VARINA
north carolina

TOWN OF FUQUAY-VARINA

PROJECT: TIP: BL-00092 ALSTON RIDGE GREENWAY

NO.	DATE	REVISIONS

TITLE: EROSION CONTROL PLANS

KHA PROJECT: 012622018

DATE: 8/13/2024

FINAL PLANS

ERO-4

K:\RAL_Roadway\012622018A - Alston Ridge Greenway\Plan\Erosion Control\Alston_ero_pst_L_C&G.dgn 8/13/2024

NOTE: SLOPES ON THIS PROJECT ARE PRIMARILY 2:1 AND 3:1. CONTRACTOR SHALL PROVIDE SOIL STABILIZATION ON ALL SLOPES WITHIN 7 DAYS OR AS REQUIRED BY NPDES GENERAL STORMWATER PERMIT. REFER TO CROSS SECTIONS AND MATTING SUMMARY SHEET.

LIMITS OF DISTURBANCE SHOWN SHADED ON SHEET EC-1. SYMBOLOLOGY IS SHOWN IN LEGEND AND IT IS DELINEATED ON THE REMAINING EROSION CONTROL PLAN SHEETS

ROCK CHECK DAMS TO BE INSTALLED AND MAINTAINED WHEN UNSTABLE AND SEDIMENT LADEN SOIL IS DRAINING TO STRUCTURES. CONTRACTOR TO COORDINATE WITH CITY INSPECTOR TO DETERMINE WHEN ROCK CHECK DAMS MAY BE REPLACED BY WATTLES UPON PARTIAL STABILIZATION OF SOIL.

BOARDWALK AND CULVERT EROSION CONTROL PHASING:

- 1. CONTRACTOR TO INSTALL ALL EROSION CONTROL MEASURES BEFORE ANY CLEARING AND GRUBBING IS PERFORMED.**
- 2. CONTRACTOR TO ACCESS BOARDWALK AND CULVERT LOCATIONS USING PROPOSED GREENWAY PATH FOOTPRINT. USE MUD MATS (SEE EROSION CONTROL DETAILS) IN WETLAND AREAS AND OTHER LOW AREAS TO LIMIT IMPACTS.**
- 3. CONTRACTOR TO DEWATER EXCAVATED AREAS AS NEEDED USING IMPERVIOUS DIKES, SPECIAL STILLING BASINS, AND BYPASSING PUMPING (DEWATERING METHOD INCIDENTAL TO BOARDWALK INSTALLATION).**
- 4. AFTER BOARDWALK AND CULVERTS ARE SET, CONTRACTOR IS TO STABILIZE ALL DISTURBED AREAS AND STREAM BANK SLOPES USING EROSION CONTROL MATTING, SEEDING (SEE SHEETS ERO-9), AND MULCH TO MAINTAIN A VIGOROUS, DENSE, VEGETATIVE COVER.**

PIPES SHALL BE INSTALLED IN THE DRY (WITH A MIN. 3 DAYS OF DRY WEATHER DURING INSTALLATION.) CONTACT ENGINEER AND INSPECTOR 24 HOURS PRIOR TO INSTALLATION OF STORMDRAIN SYSTEMS.

THESE EROSION AND SEDIMENT CONTROL PLANS COMPLY WITH THE REGULATIONS SET FORTH BY THE NCG-010000 GENERAL CONSTRUCTION PERMIT EFFECTIVE MARCH 31, 2024 ISSUED BY THE NORTH CAROLINA DEPARTMENT OF ENVIRONMENT AND NATURAL RESOURCES DIVISION OF WATER QUALITY.


SELF-INSPECTIONS AND SELF-MONITORING SHALL BE CONDUCTED IN ACCORDANCE WITH THE CONDITIONS OF THE NPDES PERMIT NO. NCG010000 AND NORTH CAROLINA GENERAL STATUTE 113A-54.1(e) AND 15A NCAC 04B.0131

THIS SHEET REPRESENTS THE CONSTRUCTION PHASE OF THE PROJECT. SEE SHEET ERO-3 FOR THE CLEARING & GRUBBING PHASE.

PLANS PREPARED BY:

Kimley Horn

300 S. MAIN ST., SUITE 202
HOLLY SPRINGS, NC 27540
PHONE: (919) 877-2000
FAX: (919) 677-2050
NC LICENSE # 0002
© 2024



NO.	DATE	REVISIONS

PLANS PREPARED FOR:
FUQUAY-VARINA
north carolina
TOWN OF FUQUAY-VARINA


PROJECT:
TIP: BL-00092
ALSTON RIDGE GREENWAY

TITLE:
EROSION CONTROL PLANS

KHA PROJECT:
012622018
DATE:
8/13/2024

FINAL PLANS

ERO-6



LEGEND

CONSTRUCTION LIMIT	C F	LIMITS OF DISTURBANCE (LABELED ON PLANS)	---
TEMPORARY SILT FENCE (SEE DETAIL SHEETS)		STORM DRAIN INLET PROTECTION (SEE DETAIL SHEETS)	□
SPECIAL SEDIMENT CONTROL FENCE / SILT FENCE OUTLET (SEE DETAIL SHEETS)	∇	TEMPORARY ROCK SILT CHECK, TYPE A (SEE NCDOT STD.1633.01)	⊗
TEMPORARY CONSTRUCTION ENTRANCE (SEE NCDOT STD.1607.01)	■	TEMPORARY ROCK SILT CHECK, TYPE B (SEE DETAIL SHEETS)	▶
ROCK PIPE INLET SEDIMENT TRAP, TYPE B (SEE NCDOT STD.1635.02)	⊙	TREE PROTECTION (SEE DETAIL SHEETS)	○
CONCRETE WASHOUT (SEE DETAIL SHEETS)	□	WATTLE (SEE DETAIL SHEETS)	⌒
OUTLET PROTECTION (SEE DETAIL SHEETS)	⊠	EXISTING CONTOUR	- - -
		PROPOSED CONTOUR	---

NPDES GENERAL STORMWATER PERMIT SOIL STABILIZATION TIMEFRAMES

SITE DESCRIPTION	STABILIZATION TIME	TIMEFRAME EXCEPTIONS
PERIMETER DIKES, SWALES, DITCHES AND SLOPES	7 DAYS	NONE
HIGH QUALITY WATER (HQW) ZONES	7 DAYS	NONE
SLOPES STEEPER THAN 3H	7 DAYS	IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2H, 14 DAYS ARE ALLOWED.
SLOPES 3H OR FLATTER	14 DAYS	7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH.
ALL OTHER AREAS WITH SLOPES FLATTER THAN 4H	14 DAYS	NONE, EXCEPT FOR PERIMETERS AND HQW ZONES.

- GENERAL NOTES (TYPICAL ALL SHEETS):**
- WHERE SILT FENCES ARE LOCATED BELOW STORM DRAIN OUTLETS, THEIR LOCATIONS MUST BE MODIFIED AS THE STORM DRAINS ARE INSTALLED SO THAT THE FENCES WILL PASS OVER THE PIPE OUTLETS.
 - SILT FENCE OUTLET MUST BE ADDED IN THE FIELD WHENEVER LOW POINTS ARE ENCOUNTERED ALONG SILT FENCE RUNS.
 - USE ROLLED EROSION CONTROL PRODUCTS ON ALL CUT/FILL SLOPES INCLUDING BASINS AS NECESSARY FOR STABILIZATION
 - DO NOT ALLOW CONCRETE DUST/WASTE/WASTEWATER INTO STORM DRAIN OR OFF-SITE. ALL SEDIMENT MUST BE CLEANED OFF THE ROADWAY BY DRY SWEEPING METHODS ONLY. WATER MUST NOT BE USED TO WASH SEDIMENT OFF OF ROADS, DRIVEWAYS, OR PARKING LOTS.
 - MINIMIZE BUFFER DISTURBANCE AS MUCH AS POSSIBLE. WORK WITHIN BUFFER ZONE SHOULD BE SEQUENCED TO MINIMIZE THE LENGTH OF TIME THAT DISTURBED AREAS ARE EXPOSED.

- GENERAL NOTES (CONT) (TYPICAL ALL SHEETS):**
- STREAM BANK STABILIZATION SHOULD BE PHASED SO THAT EACH DAY'S WORK IS COMPLETED AND ADEQUATELY STABILIZED AT THE END OF EACH WORK DAY.
 - ADEQUATE TEMPORARY SEDIMENT CONTROLS SHALL BE PROVIDED AT THE END OF EACH WORK DAY AT ALL STREAM CROSSINGS UNTIL ADEQUATE PERMANENT GROUND COVER IS PROVIDED.

K:\RAL_Roadway\012622018A - Alston Ridge Greenway\Plan\Erosion Control\Alston_ero_psh_5_F.dgn 8/13/2024

CONSTRUCTION SCHEDULE

CONSTRUCTION SPECIFICATIONS

1. Please refer to the Erosion and Sediment Control plans for detailed construction scheduling and sequencing.
2. Obtain plan approval and other applicable permits including grading permits for borrow site. Refer to Section 230 "Borrow Excavation" in the 2024 NCDOT Standard Specifications.
3. Flag the work limits for protection.
4. Hold preconstruction conference at least one week prior to starting construction and Invite NCDEQ Liaison. Please contact NCDEQ Liaison David Lee at (919) 791-4200.
5. Prior to any land disturbing (including demolition) activities, install clean water diversion ditches, fabric/block and gravel drop inlet protection, temporary gravel construction entrance/exits, check dams, tree protection fence, temporary rock silt checks, concrete washout structures, and silt fence as shown on the erosion control plans.
6. In accordance with the erosion control plans and traffic control plans: install inlet protection and erosion control measures. After inlet protection and erosion control measures are in place, grade roadway, install storm drain system. Until boxes are built and yard inlet devices installed, install and maintain storm drain under construction at end of day or onset of rain. Place outlet protection as shown on plans. Place additional check dams and stabilized ditches as indicated. Modify silt fence placement around pipe inlets and outlets as necessary, place silt fence around top of proposed headwalls.
7. Complete final grading for roads and stabilize with gravel.
8. Finish drainage inlets, place curb and gutter and pavement, and build shoulders.
9. Finish grading of slopes, topsoil critical areas and permanently vegetate, seed and mulch.
10. Vegetation along stream banks should be cut and root mat/stumps left to stabilize bank until such time as construction activity warrants their removal.
11. All graded areas will be seeded, fertilized and mulched according to NCDOT specifications to maintain a vigorous, dense, vegetative cover within 21 calendar days or sooner of completion of any phase of grading. If work on the project ceases for more than the aforementioned length of time, all disturbed areas shall have temporary vegetative ground cover established and erosion control devices maintained.
12. After seeding is established, the contractor shall call NCDEQ and arrange for a final site inspection. Upon approval, all temporary erosion control measures shall be removed from the project.
13. All erosion and sediment control practices will be inspected weekly and after rainfall events. Needed repairs will be made immediately to restore sediment containment.
14. All applicable erosion and sediment control must be maintained until a vigorous stand of permanent ground cover is established and permanent vegetation is well established. Estimated time before final stabilization is 18 months.
15. Site includes approximately 2.55 acre of permanent vegetation area.
16. After site is stabilized, temporary sediment traps, temporary diversion, construction staging and material area stockpile areas, and all other erosion control devices shall be removed, restored as existing, and permanently vegetated as described in the maintenance and vegetative plan.

MAINTENANCE

Follow the construction sequence throughout project development. When changes in construction activities are needed, amend the sequence schedule in advance to maintain management control.

Notification of Land Resources Sediment and Erosion Control Self-Inspection Program:

The Sedimentation Pollution Control Act was amended in 2006 to require that persons responsible for land-disturbing activities inspect a project after each phase of the project to make sure that the approved erosion and sedimentation control plan is being followed. Rules detailing the documentation of these inspections took effect October 1, 2010. The self-inspection program is separate from the weekly self-monitoring program of the NPDES Stormwater Permit for Construction Activities. The focus of the self-inspection report is the installation and maintenance of erosion and sedimentation control measures according to the approved plan. The inspections must be conducted after each phase of the project, and continue until permanent ground cover is established in accordance with NCGS 113A-54J and 15A NCAC 4B.0131. The Self-Inspection Report

form is available as a Word Document and PDF from at <https://www.deq.nc.gov/about/divisions/energy-mineral-and-land-resources/erosion-and-sediment-control/erosion-and-sediment-control-forms>. If you have questions or cannot access the form, please contact NCDEQ Liaison David Lee at (919) 791-4200.

MAINTENANCE PLAN

1. The Contractor shall check all erosion and sediment control practices for stability and operation following every runoff producing rainfall but in no case less than once every week. Any needed repairs will be made immediately by the Contractor to maintain all practices as designed. Also per National Pollutant Discharge Elimination System (NPDES) general stormwater permit, a rain gauge must be installed on site. The rain gauge must be kept onsite and inspections by the contractor must be made and logged after every half inch of rainfall and once a week.
2. The Contractor shall remove sediment from sediment trap when storage capacity has been approximately 50% filled. Gravel will be cleaned or replaced when the sediment pool no longer drains properly.
3. The Contractor shall remove sediment from behind silt fence when it becomes 0.5 feet deep at the fence. Silt fence will be repaired as necessary to maintain a barrier.
4. The Contractor shall fertilize, reseed as necessary, and mulch all seeded areas according to specifications in the vegetative plan to maintain a vigorous, dense vegetative cover.
5. The angle for graded slopes and fills shall be no greater than the angle that can be retained by vegetative cover or other adequate erosion-control devices or structures. In any event, slopes left exposed will, within 7 or 14 calendar days of completion of any phase of grading, be planted or otherwise provided with temporary ground cover, devices or structures sufficient to restrain erosion. Permanent groundcover will be provided for all disturbed areas within 15 working days or no more than 90 calendar days (whichever is shorter) following completion of construction.
6. The Town of Fuquay-Varina contact is Matt Paling (919) 753-1035.

RIP RAP (6.15)

CONSTRUCTION SPECIFICATIONS

Subgrade Preparation - Prepare the subgrade for riprap and filter to the required lines and grades shown on the plans. Compact any fill required in the subgrade to a density approximating that of the surrounding undisturbed material or overfill depressions with riprap. Remove brush, trees, stumps and other objectionable material. Cut the subgrade sufficiently deep that the finished grade of the riprap will be at the elevation of the surrounding area. Channels should be excavated sufficiently to allow placement of the riprap in a manner such that the finished inside dimensions and grade of the riprap meet design specifications.

Sand and gravel filter blanket - Place the filter blanket immediately after the ground foundation is prepared. For gravel, spread the filter stone in a uniform layer to the specified depth. Where more than one layer of filter material is used, spread the layers with minimal mixing.

Synthetic filter fabric - Place the cloth filter directly on the prepared foundation. Overlap the edges by at least 12 inches, and space anchor pins every 3 ft along the overlap. Bury the upstream end of the cloth a minimum of 12 inches below ground and where necessary, bury the lower end of the cloth or overlap with the next section as required. Take care not to damage the cloth when placing riprap. If damage occurs remove the riprap and repair the sheet by adding another layer of filter material with a minimum overlap of 12 inches around the damaged area. If extensive damage is suspected, remove and replace the entire sheet.

Where large stones are used or machine placement is difficult, a 4-inch layer of fine gravel or sand may be needed to protect the filter cloth.

Stone Placement - Placement of riprap should follow immediately after placement of the filter. Place riprap so that it forms a dense, well-graded mass of stone with a minimum of voids. The desired distribution of stones throughout the mass may be obtained by selective loading at the quarry and controlled dumping during final placement. Place riprap to its full thickness in one operation. Do not place riprap by dumping through chutes or other methods that cause segregation of stone sizes. Take care not to dislodge the underlying base or filter when placing the stones.

The finished slope should be free of pockets of small stone or clusters of large stones. Hand placing may be necessary to achieve the proper distribution of stone sizes to produce a relatively smooth, uniform surface. The finished grade of the riprap should blend with the surrounding area. No overfall or protrusion of riprap should be apparent.

MAINTENANCE

Inspect channels at regular intervals as well as after major rains, and make repairs promptly. Give special attention to the outlet and inlet sections and other points where concentrated flow enters. Carefully check stability at road crossings and look for indications of piping, scour holes, or bank failures. Make repairs immediately. Maintain all vegetation adjacent to the channel in a healthy, vigorous condition to protect the area from erosion and scour during out-of-bank flow. Control of weed and brush growth may be needed in some locations.

LAND GRADING (6.02)

CONSTRUCTION SPECIFICATIONS

1. Construct and maintain all erosion and sedimentation control practices and measures in accordance with the approved sedimentation control plan and construction schedule.

2. Remove good topsoil, as determined by a Geotechnical Engineer from areas to be graded and filled, and preserve it for use in finishing the grading of all critical areas.

3. Scarify areas to be topsoiled to a minimum depth of 2 inches before placing topsoil.

4. Clear and grub areas to be filled to remove trees, vegetation, roots, or other objectionable material that would affect the planned stability of the fill.

5. Ensure that fill material is free of brush, rubbish, rocks, logs, stumps, building debris, and other materials inappropriate for constructing stable fills.

6. Place all fill in layers not to exceed 9 inches in thickness, and compact the layers as required to reduce erosion, slippage, settlement, or other related problems.

7. Do not incorporate frozen material or soft or highly compressible materials into fill slopes.

8. Do not place fill on a frozen foundation, due to possible subsidence and slippage.

9. Keep diversions and other water conveyance measures free of sediment during all phases of development.

10. Handle seeps or springs encountered during construction in accordance with approved methods.

11. Permanently stabilize all graded areas immediately after final grading is completed on each area in the grading plan. Apply temporary stabilization measures on all graded areas when work is to be interrupted or delayed for 15 working days or longer.

12. Show topsoil stockpiles, borrow areas, and spoil areas on the plans, and make sure they are adequately protected from erosion. Include final stabilization of these areas in the plan.

MAINTENANCE

Periodically check all graded areas and the supporting erosion and sedimentation control practices, especially after heavy rainfalls. Promptly remove all sediment from diversion and other water disposal practices. If washouts or breaks occur, repair them immediately. Prompt maintenance of small eroded areas before they become significant gullies is an essential part of an effective erosion and sedimentation control plan.

VEGETATIVE PLAN (6.11)

SEEDING SCHEDULE

Date	Shoulders, Side Ditches, Slopes (3:1)	Planting Rate
Aug. 15 - Nov. 1	Tall Fescue	250 lbs./acre
Nov. 1 - Mar. 1	Tall Fescue & Abruzzi Rye	250 lbs./acre
Mar. 1 - Apr. 15	Tall Fescue	250 lbs./acre
Apr. 15 - Jun. 15	Hulled Common Bermudagrass	12 lbs./acre
Jun. 15 - Aug. 15	Tall Fescue & Browntop Millet ***	60 lbs./acre
	or Sorghum-Sudan Hybrids ***	35 lbs./acre
	or Sorghum-Sudan Hybrids ***	30 lbs./acre
Mar. 1 - Jun. 1	Sericea Lespedeza (scarified) and	50 lbs./acre
(Mar. 1 - Apr. 15)	Add Tall Fescue	60 lbs./acre
(Mar. 1 - Jun. 30)	or Add Weeping Lovegrass	5 lbs./acre
(Mar. 1 - Jun. 30)	or Add Hulled Common Bermudagrass	8 lbs./acre
Jun. 1 - Sep. 1	Tall Fescue ***	60 lbs./acre
	& Browntop Millet ***	35 lbs./acre
	or Sorghum-Sudan Hybrids ***	30 lbs./acre
Sep. 1 - Mar. 1	Sericea Lespedeza (unhulled-unscarified)	70 lbs./acre
	& Tall Fescue	50 lbs./acre
(Nov. 1 - Mar. 1)	Add Abruzzi Rye	25 lbs./acre

Consult Conservation Engineer or Soil Conservation Service for additional information concerning other alternatives for vegetation of denuded areas. The above vegetation rates are those which do well under local conditions; other seeding rate combinations are possible.

*** Temporary - Reseed according to optimum season for desired permanent vegetation. Do not allow temporary cover to grow over 12 inches in height before mowing, otherwise, fescue may be shaded out.

SEEDING SPECIFICATIONS


- 1) After rough grading is completed, till soil in areas to be seeded and planted to a depth of six inches.
- 2) Apply agricultural lime, fertilizer, and superphosphate to disturbed areas to be vegetated. A minimum of 2 tons limestone/acre with 3 tons limestone/acre in clay soils or per soils test 35 lbs. 10-10-10 fertilizer/1000 sq. ft. (1500 lbs./acre) 40 lbs. 50% superphosphate/1000 sq. ft. (1750 lbs./acre)
- 3) Disk nutrients into soil to a depth of six inches until surface is uniform and free of large dirt clods.
- 4) Seeding permanent grass. 3.0 lbs. KY-31 tall fescue/1000 sq. ft. (130 lbs./acre) during February 15 through May 15 or August 15 through November 15. -OR- 3.0 lbs. KY-31 tall fescue and 2.0 lbs. annual ryegrass/1000 sq. ft. during November 15 through February 15.
- 5) Mulch seeded area with small grain straw at 90 lbs./1000 sq. ft. (2 tons/acre). Spread uniformly. Approximately 1/2 of ground surface should be visible to avoid blocking sunlight to seedlings. On areas where the ground surface equals or exceeds a 3:1 slope, and in the inverts of all drainage swales, tack mulch with asphalt emulsion at a rate of 400 gallons emulsion per acre of straw.
- 6) Mulch around shrubbery and trees with pine straw to depth of 3 inches.
- 7) Temporary cover 1.0 lbs. brown top millet/1000 sq. ft. May through August 25. -OR- 1.0 lbs. annual ryegrass/1000 sq. ft. August 25 through April.
- 6) Maintenance: Refertilize if growth is not fully adequate. Reseed, refertilize and mulch immediately following erosion or other damage.

NOTE: For Riparian Buffer areas, see Sheet ERO-6 for seeding plan.

PLANS PREPARED BY:

Kimley Horn

300 S. MAIN ST., SUITE 202
 HOLLY SPRINGS, NC 27540
 PHONE: (919) 877-2000
 FAX: (919) 677-2050
 NC LICENSE #F-0002
 © 2024



SEAL

NO.	DATE	REVISIONS






PROJECT: TIP: BL-00092 ALSTON RIDGE GREENWAY

TITLE: EROSION CONTROL DETAILS



KHA PROJECT: 012622018
 DATE: 8/13/2024

FINAL PLANS

ERO-8



NO.	DATE	REVISIONS



PLANS PREPARED FOR:
FUQUAY-VARINA
north carolina

PROJECT:
TIP: BL-00092
ALSTON RIDGE GREENWAY


TITLE:
EROSION CONTROL DETAILS

KHA PROJECT:
012622018
 DATE:
8/13/2024


FINAL PLANS

ERO-10

K:\PAL_Roadway\012622018A - Alston Ridge Greenway\Plan\Erosion Control\Alston_ero_pst_detail.dgn 8/13/2024



TEMPORARY GRAVEL CONSTRUCTION ENTRANCE/EXIT (6.06.1)



NOTES:
PUT SILT FENCE OR TREE PROTECTION FENCE UP TO ENSURE CONSTRUCTION ENTRANCE IS USED.

CONSTRUCTION SPECIFICATIONS

1. Clear the entrance and exit area of all vegetation, roots, and other objectionable material and properly grade it.
2. Place the stone to the specific grade and dimensions shown on the plans, and smooth it.
3. Provide drainage to carry water to a sediment trap or other suitable outlet.
4. Use geotextile fabrics because they improve stability of the foundation in locations subject to seepage or high water table.
5. Use 2-3" coarse aggregate base course or larger.
6. Payment shall be made at the contract unit price per ton "Incidental Stone Base."


MAINTENANCE

Maintain the stone pad in a condition to prevent mud or sediment from leaving the construction site. This may require periodic tamping with 2-inch stone. After each rainfall, inspect any structure used to trap sediment and clean it out as necessary. Immediately remove all objectionable materials spilled, washed, or tracked onto public roadways.

Installation: Avoid curves in public roads and steep slopes. Remove all vegetation and other objectionable material from the foundation area. Grade and crown foundation for positive drainage.

If the slope toward the road exceeds 2%, construct a ridge, 6 to 8 inches high with 3:1 side slopes, across the foundation approximately 15 feet from the entrance to divert runoff away from the public road.

OUTLET STABILIZATION STRUCTURE DETAIL



CONSTRUCTION SPECIFICATIONS

1. Ensure that the subgrade for the filter and riprap follows the required lines and grades shown in the plan. Compact any fill required in the subgrade to the density of the surrounding undisturbed material. Low areas in the subgrade on undisturbed soil may also be filled by increasing the riprap thickness.
2. The riprap and gravel filter must conform to the specified grading limits shown on the plans.
3. Filter cloth, when used, must meet design requirements and be properly protected from punching or tearing during installation. Repair any damage by removing the riprap and placing another piece of filter cloth over the damaged area. All connecting joints should overlap a minimum of 1 foot. If damage is extensive, replace the entire filter cloth.
4. Riprap may be placed by equipment, but take care to avoid damaging the filter.
5. The minimum thickness of the riprap should be 1.5 times the maximum stone diameter.


6. Riprap may be field stone or rough quarry stone. It should be hard, angular, highly weather-resistant and well graded.
7. Construct the apron on zero grade with no overfall at the end. Make the top of the riprap at the downstream end level with the receiving area or slightly below it.
8. Ensure that the apron is properly aligned with the receiving stream and preferably straight throughout its length. If a curve is needed to fit site conditions, place it in the upper section of the apron.
9. Immediately after construction, stabilize all disturbed areas with vegetation.

MAINTENANCE

Inspect riprap outlet structures after heavy rains to see if any erosion around or below the riprap has taken place or if stones have been dislodged. Immediately make all needed repairs to prevent further damage.

NOTES

- USE CLASS A EROSION CONTROL STONE FOR STRUCTURAL STONE.
- USE NO. 5 OR NO. 57 STONE FOR SEDIMENT CONTROL STONE.
- CONSTRUCT TOP OF BERM A MINIMUM OF ONE FOOT BELOW THE SHOULDER OR DIVERSION POINT.
- PROVIDE A TOTAL SEDIMENT TRAP VOLUME OF 3600± CUBIC FEET PER ACRE OF DISTURBED AREA. SOME OF THE REQUIRED VOLUME MAY BE PROVIDED BY UP OR DOWNSTREAM CONTROLS.




MAINTENANCE

INSPECT ROCK PIPE INLET PROTECTION DEVICES AND CHANNELS FOR DAMAGE AFTER EACH RUNOFF EVENT. ANTICIPATE SUBMERGENCE AND DEPOSITION ABOVE THE ROCK PIPE INLET PROTECTION DEVICE AND EROSION FROM HIGH FLOWS AROUND THE EDGES OF THE DEVICE. CORRECT ALL DAMAGE IMMEDIATELY. IF SIGNIFICANT EROSION OCCURS, INSTALL A PROTECTIVE RIPRAP LINER IN THAT PORTION OF THE CHANNEL. REMOVE SEDIMENT ACCUMULATED BEHIND THE DEVICE AS NEEDED TO PREVENT DAMAGE TO THE DEVICE AND CONTINUATION OF THE FLOW INTO THE PIPE. ALLOW THE CHANNEL TO DRAIN THROUGH THE DEVICE, AND PREVENT LARGE FLOWS FROM CARRYING SEDIMENT OVER THE DEVICE. ADD STONES TO DAMS AS NEEDED TO MAINTAIN DESIGN HEIGHT AND CROSS SECTION.

STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.
ROADWAY STANDARD DRAWING FOR
ROCK PIPE INLET SEDIMENT TRAP TYPE B
SHEET 1 OF 1
1635.02

TEMPORARY DIVERSION DITCH DETAIL (6.20)



CONSTRUCTION SPECIFICATIONS

1. Remove and properly dispose of all trees, brush, stumps, and other objectionable material.
2. Ensure that the minimum constructed cross section meets all design requirements.
3. Ensure that the top of the dike is not lower at any point than the design elevation plus the specified settlement.
4. Provide sufficient room around diversions to permit machine regrading and cleanout.
5. Vegetate the ridge immediately after construction, unless it will remain in place less than 30 working days.
6. Use temporary liner where noted on plans.
7. Temporary diversion ditch construction shall be paid for at the contract unit price per cubic yard "Drainage Ditch Excavation."

MAINTENANCE

Inspect temporary diversions once a week and after every rainfall. Immediately remove sediment from the flow area and repair the diversion ridge. Carefully check outlets and make timely repairs as needed. When the area protected is permanently stabilized, remove the ridge and the channel to blend with the natural ground level and appropriately stabilize it.

NO.	DATE	REVISIONS

PLANS PREPARED FOR:
FUQUAY-VARINA
north carolina
TOWN OF FUQUAY-VARINA

PROJECT:
TIP: BL-00092
ALSTON RIDGE GREENWAY


TITLE:
EROSION CONTROL DETAILS

KHA PROJECT:
012622018
DATE:
8/13/2024


FINAL PLANS

ERO-11


K:\PAL_Roadway\012622018A - Alston Ridge Greenway\Plan\Erosion Control\Alston_ero_pst_detail.scdgn 8/13/2024




RIPRAP CHANNELS (6.31)



PARABOLIC-SHAPED WATERWAY WITH STONE CENTER DRAIN (SHAPED BY BULLDOZER)



V-SHAPED WATERWAY WITH STONE CENTER DRAIN (SHAPED BY MOTOR GRADER)



TABLE

STONE CLASSIFICATION	RIP RAP DEPTH
A	9"
B	18"
CLASS 1	24"
CLASS 2	24"-36"

NOTE:
 1. TO BE USED WHERE EXCESSIVE STORMWATER VELOCITIES PROHIBIT VEGETATIVE LININGS.
 2. SIZE OF STONE MUST BE DETERMINED BY APPROPRIATE DESIGN PROCEDURE.
 3. DIMENSIONS FOR D & W VARIES ACCORDING TO DESIGN.
 4. RIP RAP DEPTH AS PER DESIGN OR REFER TO TABLE.

CONSTRUCTION SPECIFICATIONS




1. Clear the foundation area of trees, stumps, roots, loose rock, and other objectionable material.
2. Excavate the cross section to the lines and grades of the foundation of the liner as shown on the plans. Bring over-excavated areas to grade by increasing the thickness of the liner or by backfilling with moist soil compacted to the density of the surrounding material.
3. Rock riprap linings: Practice 6J5, Riprap.
4. Place filters, beddings, and foundation drains to line and grade in the manner specified. Place filter and bedding materials immediately after slope preparation. For synthetic filter fabrics, overlap the downstream edge by at least 12 inches with the upstream edge which is buried a minimum 12 inches in a trench. See figure 6J4a, page 6J4.6. Space anchor pins every 3 feet along the overlap. Spread granular materials in a uniform layer. When more than one gradation is required, spread the layers so there is minimal mixing. Filter material should consist of at least 3 inches of material on all sides of the drain pipe. The drain pipe conduit should be a minimum of 4 inches in diameter. Acceptable materials include perforated, continuous, closed-joint conduits of clay, concrete, metal, plastic, or other suitable material (Practice 6.81, Subsurface Drain).

5. Perform all channel construction to keep erosion and water pollution to a minimum. Immediately upon completion of the channel, vegetate all disturbed areas or otherwise protect them against soil erosion. Where channel construction will take longer than 30 days, stabilize channels by reaches.

MAINTENANCE

Inspect channels at regular intervals as well as after major rains, and make repairs promptly. Give special attention to the outlet and inlet sections and other points where concentrated flow enters. Carefully check stability at road crossings, and look for indications of piping, scour holes, or bank failures. Make repairs immediately. Maintain all vegetation adjacent to the channel in a healthy, vigorous condition to protect the area from erosion and scour during out-of-bank flow.

TEMPORARY STREAM CROSSING (6.70)



ALTERNATE TEMPORARY STREAM CROSSING (BRIDGEMAT)
 NOT TO SCALE

CONSTRUCTION SPECIFICATIONS

1. Keep clearing and excavation of the stream banks and bed and approach sections to a minimum.
2. Divert all surface water from the construction site onto undisturbed areas adjoining the stream.
3. Keep stream crossing at right angles to the stream flow.
4. Align road approaches with the center line of the crossing for a minimum distance of 30 feet. Raise bridge abutments and culvert fills a minimum of 1 foot above the adjoining approach sections to prevent erosion from surface runoff and to allow flood flows to pass around the structure.
5. Stabilize all disturbed areas subject to flowing water, including planned overflow areas, with riprap or other suitable means if design velocity exceeds the allowable for the in-place soil.
6. Ensure that bypass channels necessary to dewater the crossing site are stable before diverting the stream. Upon completion of the crossing, fill, compact, and stabilize the bypass channel appropriately.
7. Remove temporary stream crossings immediately when they are no longer needed. Restore the stream channel to its original cross-section, and smooth and appropriately stabilize all disturbed areas.
8. Any in-stream control measures must be removed upon stabilization of the area.

MAINTENANCE

Inspect temporary stream crossings after runoff-producing rains to check for blockage in channel, erosion of abutments, channel scour, riprap displacement, or piping. Make all repairs immediately to prevent further damage to the installation.

K:\PAL_Roadway\012622018A - Alston Ridge Greenway\Plan\Erosion Control\Alston_ero_psh_detail.sdg 8/13/2024

NO.	DATE	REVISIONS

PLANS PREPARED FOR:
FUQUAY-VARINA
 north carolina
 TOWN OF FUQUAY-VARINA

PROJECT:
 TIP: BL-00092
 ALSTON RIDGE GREENWAY

TITLE:
 EROSION CONTROL DETAILS



KHA PROJECT:
012622018
 DATE:
8/13/2024

FINAL PLANS

ERO-12

WITH LINER, NO GRAVEL APPROACH

ONSITE CONCRETE WASHOUT STRUCTURE WITH LINER



SECTION A-A



NOTES:

1. ACTUAL LOCATION DETERMINED IN FIELD
2. THE CONCRETE WASHOUT STRUCTURES SHALL BE MAINTAINED WHEN THE LIQUID AND/OR SOLID REACHES 75% OF THE STRUCTURES CAPACITY.
3. CONCRETE WASHOUT STRUCTURE NEEDS TO BE CLEARLY MARKED WITH SIGNAGE NOTING DEVICE.

PLAN

BELOW GRADE WASHOUT STRUCTURE

NOT TO SCALE



NOTES:


1. ACTUAL LOCATION DETERMINED IN FIELD
2. THE CONCRETE WASHOUT STRUCTURES SHALL BE MAINTAINED WHEN THE LIQUID AND/OR SOLID REACHES 75% OF THE STRUCTURES CAPACITY TO PROVIDE ADEQUATE HOLDING CAPACITY WITH A MINIMUM 12 INCHES OF FREEBOARD.
3. CONCRETE WASHOUT STRUCTURE NEEDS TO BE CLEARLY MARKED WITH SIGNAGE NOTING DEVICE.

PLAN

ABOVE GRADE WASHOUT STRUCTURE

NOT TO SCALE


PRELIMINARY DESIGN
NOT FOR CONSTRUCTION



MUD MAT DETAIL

- NOTES:
1. MUD MAT(S) SHOULD BE LOCATED TO PROVIDE FOR UTILIZATION BY ALL CONSTRUCTION VEHICLES.
 2. MUST BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR DIRECT FLOW OF MUD INTO WETLAND.
 3. MUD MAT(S) SHALL BE UTILIZED IN WETLAND AREAS TO LIMIT IMPACTS FOR BRIDGE AND BOARDWALK CONSTRUCTION. FREQUENT CHECKS OF THE DEVICE AND TIMELY MAINTENANCE MUST BE PROVIDED BY THE CONTRACTOR.
 4. NUMBER AND LOCATION OF MUD MATS TO MINIMIZE IMPACTS OR DETERMINED BY THE ENGINEER.
 5. CONTRACTOR MAY SUBMIT ALTERNATE MUD MAT FOR APPROVAL.
 6. CONSTRUCTION ENTRANCE APPROACHES TO MUD MAT SHALL BE INCIDENTAL TO THE MUD MAT PAY ITEM.

TEMPORARY LINERS (RECP'S)



CONSTRUCTION SPECIFICATIONS

Grade the surface of installation areas so that the ground is smooth and loose. When seeding prior to installation, follow the steps for seed bed preparation, soil amendments, and seeding. All gullies, rills, and any other disturbed areas must be filled and graded prior to installation. Spread seed before RECP installation. (Important: Remove all large rocks, dirt clods, slumps, roots, grass clumps, trash, and other obstructions from the soil surface to allow for direct contact between the soil surface and the RECP.)

Terminal anchor trenches are required at RECP ends and intermittent trenches must be constructed across channels at 25-foot intervals. Terminal anchor trenches should be a minimum of 12 inches in depth and 6 inches in width, while intermittent trenches need be only 6 inches deep and 6 inches wide.

Installation for Slopes - Place the RECP 2-3 feet over the top of the slope and into an excavated end trench measuring approximately 12 inches deep by 6 inches wide. Pin the RECP at 1 foot intervals along the bottom of the trench, backfill, and compact. Unroll the RECP down (or along) the slope maintaining direct contact between the soil and the RECP. Overlap adjacent rolls a minimum of 3 inches. Pin the RECP to the ground using staples or pins in a 3 foot center-to-center pattern. Less frequent stapling/pinling is acceptable on moderate slopes.

Installation in Channels - Excavate terminal trenches (12 inches deep and 6 inches wide) across the channel at the upper and lower end of the lined channel sections. At 25-foot intervals along the channel, anchor the RECP across the channel either in 6 inch by 6 inch trenches or by installing two closely spaced rows of anchors. Excavate longitudinal trenches 6 inches deep and wide along channel edges (above water line) in which to bury the outside RECP edges. Place the first RECP at the downstream end of the channel. Place the end of the first RECP in the terminal trench and pin it at 1 foot intervals along the bottom of the trench.

Once pinned and backfilled, the RECP is deployed by wrapping over the top of the trench and unrolling upstream. If the channel is wider than the provided rolls, place ends of adjacent rolls in the terminal trench, overlapping the adjacent rolls a minimum of 3 inches. Pin at 1 foot intervals, backfill, and compact. Unroll the RECP in the upstream direction until reaching the first intermittent trench. Fold the RECP back over itself, positioning the roll on the downstream side of the trench and allowing the mat to conform to the trench.

MAINTENANCE

1. Inspect Rolled Erosion Control Products at least weekly and after each significant (1/2 inch or greater) rain fall event repair immediately.
2. Good contact with the ground must be maintained, and erosion must not occur beneath the RECP.
3. Any areas of the RECP that are damaged or not in close contact with the ground shall be repaired and stapled.
4. If erosion occurs due to poorly controlled drainage, the problem shall be fixed and the eroded area protected.
5. Monitor and repair the RECP as necessary until ground cover is established.

NOTES:

1. Design velocities exceeding 2 ft/sec require temporary blankets, mats or similar liners to protect seed and soil until vegetation becomes established.
2. Grass-lined channels with design velocities exceeding 6 ft/sec should include turf reinforcement mats.

Table 6.17b Permissible Shear Stress, τ_c , of Various RECP's


Category	Product Type	Max. Permissible Shear Stress (lb/ft ²)	Slopes* Up To
Degradable RECP's (Unvegetated)	Nets and Mulch	0.1 - 0.2	20:1
	Coir Mesh	0.4 - 3.0	3:1
	Blanket - Single Net	1.55 - 2.0	2:1
	Blanket - Double Net	1.65 - 3.0	1:1
Nondegradable RECP's	Unvegetated TRM**	2 - 4	1:1
	Partially Vegetated TRM	4 - 6	>1:1
	Fully Vegetated	5 - 10	>1:1

* Steeper slope limits may apply. For further information, contact the manufacturer.
** Turf Reinforcement Mat.

PLANS PREPARED BY:

Kimley Horn

300 S. MAIN ST., SUITE 202
HOLLY SPRINGS, NC 27540
PHONE: (919) 877-2000
FAX: (919) 677-2050
NC LICENSE #P-0002
© 2024



SEAL

NO.	DATE	REVISIONS

PLANS PREPARED FOR:
FUQUAY-VARINA
TOWN OF FUQUAY-VARINA

PROJECT:
TIP: BL-00092
ALSTON RIDGE GREENWAY

TITLE:
EROSION CONTROL DETAILS

KHA PROJECT:
012622018
DATE:
8/13/2024

FINAL PLANS

ERO-13

K:\PAL_Roadway\012622018.A - Alston Ridge Greenway\Plan\Erosion Control\Alston_ero_pst_detail.scd

8/13/2024

GROUND STABILIZATION AND MATERIALS HANDLING PRACTICES FOR COMPLIANCE WITH THE NCG01 CONSTRUCTION GENERAL PERMIT
 Implementing the details and specifications on this plan sheet will result in the construction activity being compliant with the Ground Stabilization and Materials Handling sections of the NCG01 Construction General Permit (Sections E and F, respectively). The details and specifications on this plan sheet are intended to be used in conjunction with the approved ERO-14 permit and may not apply depending on site conditions and the delegated authority having jurisdiction.

SECTION E: GROUND STABILIZATION	
Site Area Description	Required Ground Stabilization Timeframes
Stabilize within this many calendar days after ceasing land disturbance	
(a) Perimeter dikes, swales, ditches, and perimeter slopes	7
(b) High Quality Water (HQW) Zones	7
(c) Slopes steeper than 3:1	7
(d) Slopes 3:1 to 4:1	14
(e) Areas with slopes flatter than 4:1	14

Note: After the permanent cessation of construction activities, any areas with temporary ground stabilization shall be converted to permanent ground stabilization as soon as practicable but in no case longer than 90 calendar days after the last land disturbing activity. Temporary ground stabilization shall be converted to permanent ground stabilization as soon as practicable to prevent accelerated erosion until permanent ground stabilization is achieved.

GROUND STABILIZATION SPECIFICATION	
Stabilize the ground sufficiently so that rain will not dislodge the soil. Use one of the techniques in the table below:	
Temporary Stabilization	Permanent Stabilization
<ul style="list-style-type: none"> Temporary grass seed covered with straw or mulch and dunnies Hydroseeding Rollered erosion control products with or without temporary grass seed Appropriately applied straw or other mulch Plastic sheeting 	<ul style="list-style-type: none"> Permanent grass seed covered with straw or mulch and dunnies Geotextile fabrics such as permanent soil reinforcement matting Hydroseeding Shrubs or other permanent plantings covered with mulch Rollered erosion control products with grass seed Structural methods such as concrete, asphalt or retaining walls Rollered erosion control products with grass seed

POLYACRYLAMIDES (PAMS) AND FLOCCULANTS
 1. Select flocculants that are appropriate for the soils being exposed during construction, steering from the NCDWR List of Approved PAMS/Flocculants.
 2. Apply flocculants at or before the inlets to Erosion and Sediment Control Measures.
 3. PAMS/Flocculants and in accordance with the manufacturer's instructions.
 4. Provide ponding area for containment of treated Stormwater before discharging offsite.
 5. Store flocculants in leak-proof containers that are kept under storm-resistant cover or surrounded by secondary containment structures.


EQUIPMENT AND VEHICLE MAINTENANCE
 1. Maintain vehicles and equipment to prevent discharge of fluids.
 2. Provide drip pans under any stored equipment.
 3. Identify leaks and repair as soon as feasible, or remove leaking equipment from the project.
 4. Collect all spent fluids, store in separate containers and properly dispose as hazardous waste (recycle when possible).
 5. Remove leaking vehicles and construction equipment from service until the problem has been corrected.
 6. Bring used fuels, lubricants, coolants, hydraulic fluids and other petroleum products to a recycling or disposal center that handles these materials.

LITTER, BUILDING MATERIAL AND LAND CLEARING WASTE
 1. Never bury or burn waste. Place litter and debris in approved waste containers.
 2. Provide a sufficient number and size of waste containers (e.g. dumpster, trash receptacle) on site to contain construction and domestic wastes.
 3. Locate waste containers at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
 4. Store building materials in neat piles and cover with tarpaulins or plastic from upland areas and does not drain directly to storm drain, stream or wetland.
 5. Cover waste containers at the end of each workday and before storm events or provide secondary containment. Repair or replace damaged waste containers.
 6. Anchor all lightweight items in waste containers during times of high winds.
 7. Empty all lightweight items as needed to prevent overflowing. Clean up immediately if containers overflow.
 8. Dispose waste off-site at an approved disposal facility.
 9. On business days, clean up and dispose of waste in designated waste containers.

PAINT AND OTHER LIQUID WASTE
 1. Do not dump paint and other liquid waste into storm drains, streams or wetlands.
 2. Locate paint washouts at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
 3. Contain liquid wastes in a controlled area.
 4. Containers must be labeled, sized and placed appropriately for the needs of site.
 5. Prevent the discharge of soaps, solvents, detergents and other liquid wastes from construction areas.

PORTABLE TOILETS
 1. Install portable toilets on level ground, at least 50 feet away from storm drains, streams or wetlands unless there is no alternative reasonably available. If 50 foot offset is not attainable, provide relocation of portable toilet behind dirt fence or place on a gravel pad and surround with sand bags.
 2. Provide stacking or anchoring of portable toilets during periods of high winds or in high foot traffic areas.
 3. Utilize all licensed sanitary waste hauler to remove existing portable toilets and replace with properly operating unit.

EARTHEN STOCKPILE MANAGEMENT
 1. Show stockpile locations on plans. Locate earthen-material stockpile areas at least 50 feet away from storm drain inlets, sediment basins, perimeter sediment controls and surface waters unless it can be shown no other alternatives are reasonably available.
 2. Protect stockpile with silt fence installed along toe of slope with a minimum offset of five feet from the toe of stockpile.
 3. Provide stable stone access point when feasible.
 4. Stabilize stockpile within the timeframes provided on this sheet and in accordance with the approved plan and any additional requirements. Soil stabilization is defined as the application of a soil stabilizer to soil to increase its strength and prevent accelerated erosion on disturbed soils for temporary or permanent control needs.



CONCRETE WASHOUTS
 1. Do not discharge concrete or cement slurry from the site.
 2. Dispose of, or recycle settled, hardened concrete residue in accordance with local and state solid waste regulations and at an approved facility.
 3. Manage washout from mortar mixers in accordance with the above item and in addition place the mixer and associated materials on impervious barrier and within 10 feet of concrete washout structure.
 4. Install temporary concrete washouts per local requirements, where applicable. If an alternate method or product is to be used, contact your approval authority for review and approval. If local standard details are not available, use one of the types of temporary concrete washouts provided on this detail.
 5. Do not use concrete washouts for dewatering or storing defective curb or sidewalk sections. Stormwater accumulated within the washout may not be pumped into or discharged to the storm drain system or receiving surface waters. Liquid waste must be pumped out of the washout from project.
 6. Washouts must be at least 50 feet from storm drain inlets and surface waters unless it can be shown that no other alternatives are reasonably available. At a minimum, install protection of storm drain inlet(s) closest to the washout which could receive spills or overflow.
 7. Locate washouts in an easily accessible area, on level ground and install a stone entrance pad in front of the washout. Additional controls may be required by the approving authority.
 8. Install at least one sign directing concrete trucks to the washout within the project limits. Post signage on the washout itself to identify this location.
 9. Washouts must be designed so that they do not allow any debris or debris to limit overflow events. Replace the brand and material of other components of structural components when no longer functional. When utilizing alternative or proprietary products, follow manufacturer's instructions.
 10. At the completion of the concrete work, remove remaining leavings and dispose of in an approved disposal facility. Fill pit, if applicable, and stabilize any disturbance caused by removal of washout.

HERBICIDES, PESTICIDES AND RODENTICIDES
 1. Store and apply herbicides, pesticides and rodenticides in accordance with label restrictions.
 2. Store herbicides, pesticides and rodenticides in their original containers with the label, which lists directions for use, ingredients and first aid steps in case of injury.
 3. Do not store herbicides, pesticides and rodenticides in areas where flooding is possible or where they may spill or leak into wells, stormwater drains, ground water or surface water. If a spill occurs, clean area immediately.
 4. Do not stockpile these materials onsite.

HAZARDOUS AND TOXIC WASTE
 1. Create designated hazardous waste collection areas on-site.
 2. Place hazardous waste containers under cover or in secondary containment.
 3. Do not store hazardous chemicals, drums or bagged materials directly on the ground.

EFFECTIVE: 04/01/19

NGG01 GROUND STABILIZATION AND MATERIALS HANDLING

EFFECTIVE: 04/01/19

PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION A: SELF-INSPECTION

Self-inspections are required during normal business hours in accordance with the table below. When adverse weather or site conditions would cause the safety of the inspection personnel to be in jeopardy, the inspection may be delayed until the next business day on which it is safe to perform the inspection. In addition, when a storm event of equal to or greater magnitude occurs, the inspection shall be delayed until the next business day. Self-inspections performed upon the commencement of the next business day. Any time when inspections were delayed shall be noted in the Inspection Report.

Inspect	Frequency (during normal business hours)	Inspection records must include:
(1) Rain gauge maintained in good working order	Daily rainfall amounts. If no daily rain gauge observations are made during weekend or holiday periods, and no individual daily rainfall information is recorded, then the total rainfall for the week must be recorded. If an amendment may have occurred during the week, the total rainfall for the week must be recorded as well. Days on which no rainfall occurred shall be recorded as zero.	1. Identification of the measures inspected.
(2) E&S Measures	At least once per week for areas with slopes greater than 2:1 to 4:1 and within 24 hours of a rain event 2.0 inch or greater.	2. Description, evidence, and date of corrective actions taken, and
(3) Stormwater outfalls (SOWs)	At least once per week for areas with slopes greater than 2:1 to 4:1 and within 24 hours of a rain event 2.0 inch or greater.	3. An explanation as to the actions taken to control future
(4) Perimeter of site	At least once per 7 calendar days and within 24 hours of a rain event 2.0 inch or greater.	4. Description, evidence, and date of corrective actions taken.
(5) Streams or wetlands onsite	At least once per 7 calendar days and within 24 hours of a rain event 2.0 inch or greater.	5. Name of the person performing the inspection,
(6) Ground stabilization measures	At least once per 7 calendar days and within 24 hours of a rain event 2.0 inch or greater.	6. Description, evidence, and date of corrective actions taken.

NOTE: The rain inspection resets the required 7 calendar day inspection requirement.

PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION B: RECORDKEEPING

The approved E&S plan as well as any approved deviation shall be kept on the site. The approved E&S plan must be kept up-to-date throughout the coverage under this permit. The following items pertaining to the E&S plan shall be kept on site and available for inspection at all times during normal business hours.

Item to Document	Documentation Requirements
(a) E&S Plan	Initial and date each E&S measure on a copy of the approved E&S plan or complete, date and sign an inspection report that lists each E&S measure shown on the approved E&S plan. Initial installation of the E&S measures or if the E&S measures are modified after initial installation.
(b) A phase of grading has been completed.	Initial and date a copy of the approved E&S plan or complete, date and sign an inspection report to indicate completion of the construction phase.
(c) Ground cover is located and installed in accordance with the approved E&S plan.	Initial and date a copy of the approved E&S plan or complete, date and sign an inspection report to indicate compliance with approved ground cover specifications.
(d) The maintenance and repair requirements for all E&S measures	Complete, date and sign an inspection report.
(e) Corrective actions have been taken to E&S measures.	Initial and date a copy of the approved E&S plan or complete, date and sign an inspection report to indicate the completion of the corrective action.

Additional Documentation to be Kept on Site
 In addition to the E&S plan documents above, the following items shall be kept on the site and available for inspectors at all times during normal business hours, unless the Division provides a site-specific exemption based on unique site conditions that make this requirement not practical:
 (a) This General Permit as well as the Certificate of Coverage, after it is received.
 (b) Records of inspections made during the previous twelve months. The permittee shall record the required observations on the Inspection Record Form provided by the Division. The records shall be maintained in an electronic format. The records shall be electronically available records in lieu of the required paper copies will be allowed if shown to provide equal access and utility as the hard-copy records.
 (c) Documentation to be Required for These Years
 All three years after project completion and made available upon request. (40 CFR 122.41)

PART II, SECTION G, ITEM (4) DRAW DOWN OF SEDIMENT BASINS FOR MAINTENANCE OR CLOSE OUT

Sediment basins and traps that receive runoff from drainage areas of one acre or more shall use outlet structures that withdraw water from the surface when these devices need to be drawn down for maintenance or close out unless this is infeasible. The circumstances in which it is not feasible to withdraw water from the surface shall be (for example, times with extended cold weather). Non-surface withdrawals from sediment basins shall be allowed only when all of the following criteria have been met:
 (a) The E&S plan authority has been provided with documentation of the non-surface withdrawal and the specific time periods or conditions in which it will occur. The non-surface withdrawal shall not commence until the E&S plan authority has approved these items.
 (b) The non-surface withdrawal has been reported as an anticipated bypass in accordance with Part III, Section C, Item (2)(c) and (d) of this permit.
 (c) Dewatering discharges are treated with controls to minimize discharges of pollutants from stormwater that is removed from the sediment basin. Examples of appropriate controls include properly sited, designed and maintained dewatering tanks, weir tanks, and filtration systems.
 (d) Vegetated, upland areas of the sites or a properly designed stone pad is used to the extent feasible at the outlet of the dewatering treatment devices described in item (c) above, and
 (e) Velocity dissipation devices such as check dams, sediment traps, and riprap are provided at the discharge points of all dewatering devices, and
 (f) Sediment removed from the dewatering treatment devices described in item (c) above is disposed of in a manner that does not cause deposition of sediment into waters of the United States.

NGG01 SELF-INSPECTION, RECORDKEEPING AND REPORTING

EFFECTIVE: 04/01/19

PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION C: REPORTING

1. Occurrences that Must be Reported

- Visible sediment deposition in a stream or wetland.
- Oil spills if:
 - They are 25 gallons or more.
 - They are less than 25 gallons but cannot be cleaned up within 24 hours, or
 - They cause sheen on surface waters (regardless of volume), or
 - They are within 100 feet of surface waters (regardless of volume).
- Releases of hazardous substances in excess of reportable quantities under Section 311 of the Clean Water Act (40 CFR 110.3 and 40 CFR 117.3) or Section 102 of CERCLA (40 CFR 302.4) or G.S. 142-15.85.
- Anticipated bypasses and unanticipated bypasses.
- Noncompliance with the conditions of this permit that may endanger health or the environment.

2. Reporting Timeframes and Other Requirements

After a permittee becomes aware of an occurrence that must be reported, he shall contact the appropriate Division regional office within the timeframes and in accordance with the other requirements listed below. Occurrences outside normal business hours may also be reported to the Department's Environmental Emergency Center personnel at (800) 858-0368.

Occurrence	Reporting Timeframes (After Discovery) and Other Requirements
(a) Visible sediment deposition in a stream or wetland	<ul style="list-style-type: none"> Within 24 hours, an oral or electronic notification. Within 7 calendar days, a report that contains a description of the occurrence, the location of the occurrence, the location of the sediment, and the location of the stream or wetland. Division staff may waive the requirement for a written report on a case-by-case basis. If the stream is named on the NC 40 CFR 110.3, it is impaired for sediment-related causes, the permittee may be required to perform additional monitoring to determine if additional requirements are needed to assure compliance with the federal or state impaired-waters conditions. Within 24 hours, an oral or electronic notification. The notification shall include information about the date, time, nature, volume and location of the spill or release.
(b) Oil spills and release of substances per item 1(b)-(c) above	<ul style="list-style-type: none"> A report or at least ten days before the date of the bypass, if possible. Within 24 hours, an oral or electronic notification. Within 7 calendar days, a report that includes an evaluation of the quality and effect of the bypass. Within 24 hours, an oral or electronic notification. Within 7 calendar days, a report that includes an evaluation of the noncompliance cause(s), the period of noncompliance, including exact dates and times, and if the noncompliance has not been corrected, the anticipated time noncompliance is expected to continue, and steps taken or planned to reduce, eliminate, and prevent the noncompliance. Division staff may waive the requirement for a written report on a case-by-case basis.
(c) Anticipated bypasses 40 CFR 122.43(m)(3)	<ul style="list-style-type: none"> Unanticipated bypasses 40 CFR 122.43(m)(3) Noncompliance with the conditions of this permit that may endanger health or the environment 40 CFR 122.43(m)(7)



EFFECTIVE: 04/01/19

NO.	DATE	REVISIONS

PLANS PREPARED FOR:

FUQUAY-VARINA
 north carolina
 TOWN OF FUQUAY-VARINA

PROJECT:
 TIP: BL-0092
 ALSTON RIDGE GREENWAY

TITLE:
 BOARDWALK DETAILS


KHA PROJECT:
012622018
 DATE:
8/13/2024

FINAL PLANS


NOTES

ALL FENCE MATERIAL SHALL MEET THE REQUIREMENTS OF SECTION 1050 OF THE NCDOT STANDARD SPECIFICATIONS. GALVANIZE ALL STEEL PARTS AND HARDWARE IN ACCORDANCE WITH ARTICLE 1079 OF THE NCDOT STANDARD SPECIFICATIONS.


ALL CHAIN LINK FENCE FABRIC, POSTS, RAILS FITTING HARDWARE AND ACCESSORIES SHALL BE BLACK VINYL COATED IN ACCORDANCE WITH ARTICLE 1050 OF THE NCDOT STANDARD SPECIFICATIONS.




PEDESTRIAN RAIL DETAIL




TYPICAL APPROACH RAIL ELEVATION



TYPICAL APPROACH RAIL PLAN



TIMBER BOARDWALK DECK FRAMING PLAN



TYPICAL SECTION THROUGH MIDSPAN

K:\RAL_Roadway\012622018A - Alston Ridge Greenway\Plan\Plan Sheets\Alston_S03.dgn
 8/13/2024

STANDARD NOTES

DESIGN DATA:

SPECIFICATIONS	-----	A.A.S.H.T.O. (CURRENT)
LIVE LOAD	-----	SEE PLANS
IMPACT ALLOWANCE	-----	SEE A.A.S.H.T.O.
STRESS IN EXTREME FIBER OF STRUCTURAL STEEL - AASHTO M270 GRADE 36	--	20,000 LBS. PER SQ. IN.
- AASHTO M270 GRADE 50W	--	27,000 LBS. PER SQ. IN.
- AASHTO M270 GRADE 50	--	27,000 LBS. PER SQ. IN.
REINFORCING STEEL IN TENSION - GRADE 60	--	24,000 LBS. PER SQ. IN.
CONCRETE IN COMPRESSION	-----	1,200 LBS. PER SQ. IN.
CONCRETE IN SHEAR	-----	SEE A.A.S.H.T.O.
STRUCTURAL TIMBER - TREATED OR UNTREATED EXTREME FIBER STRESS	---	1,800 LBS. PER SQ. IN.
COMPRESSION PERPENDICULAR TO GRAIN OF TIMBER	-----	375 LBS. PER SQ. IN.
EQUIVALENT FLUID PRESSURE OF EARTH	-----	30 LBS. PER CU. FT. (MINIMUM)

MATERIAL AND WORKMANSHIP:

EXCEPT AS MAY OTHERWISE BE SPECIFIED ON PLANS OR IN THE SPECIAL PROVISIONS, ALL MATERIAL AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE 2024 "STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES" OF THE N. C. DEPARTMENT OF TRANSPORTATION.

STEEL SHEET PILING FOR PERMANENT OR TEMPORARY APPLICATIONS SHALL BE HOT ROLLED.

CONCRETE:

UNLESS OTHERWISE REQUIRED ON PLANS, CLASS A CONCRETE SHALL BE USED FOR ALL PORTIONS OF ALL STRUCTURES WITH THE EXCEPTION THAT: CLASS AA CONCRETE SHALL BE USED IN BRIDGE SUPERSTRUCTURES, ABUTMENT BACKWALLS, AND APPROACH SLABS; AND CLASS B CONCRETE SHALL BE USED FOR SLOPE PROTECTION AND RIP RAP.

CONCRETE CHAMFERS:

UNLESS OTHERWISE NOTED ON THE PLANS, ALL EXPOSED CORNERS ON STRUCTURES SHALL BE CHAMFERED 3/4" WITH THE FOLLOWING EXCEPTIONS: TOP CORNERS OF CURBS MAY BE ROUNDED TO 1 1/2" RADIUS WHICH IS BUILT INTO CURB FORMS; CORNERS OF TRANSVERSE FLOOR EXPANSION JOINTS SHALL BE ROUNDED WITH A 1/4" FINISHING TOOL UNLESS OTHERWISE REQUIRED ON PLANS; AND CORNERS OF EXPANSION JOINTS IN THE ROADWAY FACES AND TOPS OF CURBS AND SIDEWALKS SHALL BE ROUNDED TO A 1/4" RADIUS WITH A FINISHING STONE OR TOOL UNLESS OTHERWISE REQUIRED ON PLANS.

DOWELS:

DOWELS WHEN INDICATED ON PLANS AS FOR CULVERT EXTENSIONS, SHALL BE EMBEDDED AT LEAST 12" INTO THE OLD CONCRETE AND GROUTED INTO PLACE WITH 1:2 CEMENT MORTAR.

ALLOWANCE FOR DEAD LOAD DEFLECTION, SETTLEMENT, ETC. IN CASTING SUPERSTRUCTURES:

BRIDGES SHALL BE BUILT ON THE GRADE OR VERTICAL CURVE SHOWN ON PLANS. SLABS, CURBS AND PARAPETS SHALL CONFORM TO THE GRADE OR CURVE.

ALL DIMENSIONS WHICH ARE GIVEN IN SECTION AND ARE AFFECTED BY DEAD LOAD DEFLECTIONS ARE DIMENSIONS AT CENTER LINE OF BEARING UNLESS OTHERWISE NOTED ON PLANS. IN SETTING FORMS FOR STEEL BEAM BRIDGES AND PRESTRESSED CONCRETE GIRDER BRIDGES, ADJUSTMENTS SHALL BE MADE DUE TO THE DEAD LOAD DEFLECTIONS FOR THE ELEVATIONS SHOWN. WHERE BLOCKS ARE SHOWN OVER BEAMS FOR BUILDING UP TO THE SLAB, THE VERTICAL DIMENSIONS OF THE BLOCKS SHALL BE ADJUSTED BETWEEN BEARINGS TO COMPENSATE FOR DEAD LOAD DEFLECTIONS, VERTICAL CURVE ORDINATE, AND ACTUAL BEAM CAMBER. WHERE BOTTOM OF SLAB IS IN LINE WITH BOTTOM OF TOP FLANGES, DEPTH OF SLAB BETWEEN BEARINGS SHALL BE ADJUSTED TO COMPENSATE FOR DEAD LOAD DEFLECTION, VERTICAL CURVE ORDINATE, AND ACTUAL BEAM CAMBER.

IN SETTING FALSEWORK AND FORMS FOR REINFORCED CONCRETE SPANS, AN ALLOWANCE SHALL BE MADE FOR DEAD LOAD DEFLECTIONS, SETTLEMENT OF FALSEWORK, AND PERMANENT CAMBER WHICH SHALL BE PROVIDED FOR IN ADDITION TO THE ELEVATIONS SHOWN. AFTER REMOVAL OF THE FALSEWORK, THE FINISHED STRUCTURES SHALL CONFORM TO THE PROFILE AND ELEVATIONS SHOWN ON THE PLANS AND CONSTRUCTION ELEVATIONS FURNISHED BY THE ENGINEER.

DETAILED DRAWINGS FOR FALSEWORK OR FORMS FOR BRIDGE SUPERSTRUCTURE AND ANY STRUCTURE OR PARTS OF A STRUCTURE AS NOTED ON THE PLANS SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL BEFORE CONSTRUCTION OF THE FALSEWORK OR FORMS IS STARTED.

REINFORCING STEEL:

ALL REINFORCING STEEL SHALL BE DEFORMED. DIMENSIONS RELATIVE TO PLACEMENT OF REINFORCING ARE TO CENTERS OF BARS UNLESS OTHERWISE INDICATED IN THE PLANS. DIMENSIONS ON BAR DETAILS ARE TO CENTERS OF BARS OR ARE OUT TO OUT AS INDICATED ON PLANS.

WIRE BAR SUPPORTS SHALL BE PROVIDED FOR REINFORCING STEEL WHERE INDICATED ON THE PLANS. WHEN BAR SUPPORT PIECES ARE PLACED IN CONTINUOUS LINES, THEY SHALL BE SO PLACED THAT THE ENDS OF THE SUPPORTING WIRES SHALL BE LAPPED TO LOCK LEGS ON ADJOINING PIECES.

STRUCTURAL STEEL:

AT THE CONTRACTOR'S OPTION, HE MAY SUBSTITUTE 7/8" Ø SHEAR STUDS FOR THE 3/4" Ø STUDS SPECIFIED ON THE PLANS. THIS SUBSTITUTION SHALL BE MADE AT THE RATE OF 3 - 7/8" Ø STUDS FOR 4 - 3/4" Ø STUDS, AND STUD SPACING CHANGES SHALL BE MADE AS NECESSARY TO PROVIDE THE SAME EQUIVALENT NUMBER OF 7/8" Ø STUDS ALONG THE BEAM AS SHOWN FOR 3/4" Ø STUDS BASED ON THE RATIO OF 3 - 7/8" Ø STUDS FOR 4 - 3/4" Ø STUDS. STUDS OF THE LENGTH SPECIFIED ON THE PLANS MUST BE PROVIDED. THE MAXIMUM SPACING SHALL BE 2'-0".

EXCEPT AT THE INTERIOR SUPPORTS OF CONTINUOUS BEAMS WHERE THE COVER PLATE IS IN CONTACT WITH BEARING PLATE, THE CONTRACTOR MAY, AT HIS OPTION, SUBSTITUTE FOR THE COVER PLATES DESIGNATED ON THE PLANS COVER PLATES OF THE EQUIVALENT AREA PROVIDED THESE PLATES ARE AT LEAST 5/16" IN THICKNESS AND DO NOT EXCEED A WIDTH EQUAL TO THE FLANGE WIDTH LESS 2" OR A THICKNESS EQUAL TO 2 TIMES THE FLANGE THICKNESS. THE SIZE OF FILLET WELDS SHALL CONFORM TO THE REQUIREMENTS OF THE CURRENT ANSI/AASHTO/AWS "BRIDGE WELDING CODE". ELECTROSLAG WELDING WILL NOT BE PERMITTED.

WITH THE SOLE EXCEPTION OF EDGES AT SURFACES WHICH BEAR ON OTHER SURFACES, ALL SHARP EDGES AND ENDS OF SHAPES AND PLATES SHALL BE SLIGHTLY ROUNDED BY SUITABLE MEANS TO A RADIUS OF APPROXIMATELY 1/16" INCH OR EQUIVALENT FLAT SURFACE AT A SUITABLE ANGLE PRIOR TO PAINTING, GALVANIZING, OR METALLIZING.

HANDRAILS AND POSTS:

METAL STANDARDS AND FACES OF THE CONCRETE END POSTS FOR THE METAL RAIL SHALL BE SET NORMAL TO THE GRADE OF THE CURB, UNLESS OTHERWISE SHOWN ON PLANS. THE METAL RAIL AND TOPS OF CONCRETE POSTS USED WITH THE ALUMINUM RAIL SHALL BE BUILT PARALLEL TO THE GRADE OF THE CURB.

METAL HANDRAILS SHALL BE IN ACCORDANCE WITH THE PLANS. RAILS SHALL BE AS MANUFACTURED FOR BRIDGE RAILING. CASTINGS SHALL BE OF A UNIFORM APPEARANCE. FINIS AND OTHER DEFORMATIONS RESULTING FROM CASTING OR OTHERWISE SHALL BE REMOVED IN A MANNER SO THAT A UNIFORM COLORING OF THE COMPLETED CASTING SHALL BE OBTAINED. CASTINGS WITH DISCOLORATIONS OR OF NON-UNIFORM COLORING WILL NOT BE ACCEPTED. CERTIFIED MILL REPORTS ARE REQUIRED FOR METAL RAILS AND POSTS.

SPECIAL NOTES:

GENERALLY, IN CASE OF DISCREPANCY, THIS STANDARD SHEET OF NOTES SHALL GOVERN OVER THE SPECIFICATIONS, BUT THE REMAINDER OF THE PLANS SHALL GOVERN OVER NOTES HEREON, AND SPECIAL PROVISIONS SHALL GOVERN OVER ALL. SEE SPECIFICATIONS ARTICLE 105-4.

ENGLISH


JANUARY, 1990

STD. NO. SN

PLANS PREPARED BY:



300 S MAIN ST, SUITE 202
HOLLY SPRINGS, NC 27540
PHONE: (919) 677-2000
FAX: (919) 677-2050
NC LICENSE #P-0002
©2024



ALSTON RIDGE GREENWAY CROSS SECTION INDEX

-L- (ALSTON RIDGE GREENWAY)
-Y1- (BOARDWALK LOOKOUT)

X-2 THRU X-6
X-7

NO.	DATE	REVISIONS

PLANS PREPARED FOR:



FUQUAY-VARINA
TOWN OF FUQUAY-VARINA

PROJECT:

TIP: BL-00092
ALSTON RIDGE GREENWAY

TITLE:


CROSS SECTIONS
INDEX OF SHEETS

KHA PROJECT: 012622018
DATE: 8/13/2024

FINAL PLANS

X-1

K:\PAL_Roadway\012622018.A - Alston Ridge Greenway\Plan\Cross-Sections\Alston_xpl_Index.dgn
8/13/2024



NO.	DATE	REVISIONS

PLANS PREPARED FOR:

 TOWN OF FUQUAY-VARINA

PROJECT:
 TIP: BL-00092
 ALSTON RIDGE GREENWAY


TITLE:
 CROSS SECTION SHEETS

KHA PROJECT:
012622018
 DATE:
8/13/2024


FINAL PLANS

X-2

K:\PAL_Roadway\012622018.A - Alston Ridge Greenway\Plan\Cross-Sections\Alston_xpl.Ldgn
 8/13/2024



-L- ALSTON RIDGE GREENWAY



NO.	DATE	REVISIONS

PLANS PREPARED FOR:

 TOWN OF FUQUAY-VARINA

PROJECT:
 TIP: BL-00092
 ALSTON RIDGE GREENWAY


TITLE:
 CROSS SECTION SHEETS


KHA PROJECT:
012622018
 DATE:
8/13/2024

FINAL PLANS

X-3

K:\PAL_Roadway\012622018.A - Alston Ridge Greenway\Plan\Cross-Sections\Alston_xpl.Ldgn
 8/13/2024





NO.	DATE	REVISIONS

PLANS PREPARED FOR:

TOWN OF FUQUAY-VARINA

PROJECT:

TIP: BL-00092
ALSTON RIDGE GREENWAY

TITLE:

CROSS SECTION SHEETS

KHA PROJECT:

012622018


DATE:

8/13/2024


FINAL PLANS

X-4

K:\PAL_Roadway\012622018.A - Alston Ridge Greenway\Plan\Cross-Sections\Alston_xpl.Ldgn
8/13/2024



-L- ALSTON RIDGE GREENWAY



NO.	DATE	REVISIONS

PLANS PREPARED FOR:

 TOWN OF FUQUAY-VARINA

PROJECT:
 TIP: BL-00092
 ALSTON RIDGE GREENWAY


TITLE:
 CROSS SECTION SHEETS

KHA PROJECT:
 012622018
 DATE:
 8/13/2024


FINAL PLANS

X-5

K:\PAL_Roadway\012622018.A - Alston Ridge Greenway\Plan\Cross-Sections\Alston_xpl.Ldgn
 8/13/2024



-L- ALSTON RIDGE GREENWAY



NO.	DATE	REVISIONS

PLANS PREPARED FOR:

 TOWN OF FUQUAY-VARINA

PROJECT:
 TIP: BL-00092
 ALSTON RIDGE GREENWAY


TITLE:
 CROSS SECTION SHEETS

KHA PROJECT:
 012622018
 DATE:
 8/13/2024

FINAL PLANS

X-6

K:\PAL_Roadway\012622018.A - Alston Ridge Greenway\Plan\Cross-Sections\Alston_xpl.Ldgn
 8/13/2024




-L- ALSTON RIDGE GREENWAY

PLANS PREPARED BY:

Kimley»Horn

300 S MAIN ST, SUITE 202
HOLLY SPRINGS, NC 27540
PHONE: (919) 677-2000
FAX: (919) 677-2050
NC LICENSE #F-0002
© 2024



NO.	DATE	REVISIONS

PLANS PREPARED FOR:

 TOWN OF FUQUAY-VARINA

PROJECT:
 TIP: BL-00092
 ALSTON RIDGE GREENWAY


TITLE:
 CROSS SECTION SHEETS

KHA PROJECT:
 012622018
 DATE:
 8/13/2024

FINAL PLANS

X-7

K:\PAL_Roadway\012622018.A - Alston Ridge Greenway\Plan\Cross-Sections\Alston_xpl_Y1.dgn
8/13/2024



-Y1- BOARDWALK OVERLOOK